




THE STATE OF UTAH
OFFICE OF STATE ENGINEER
SALT LAKE CITY



September 11, 1961

Phillips Petroleum Company
Bartlesville,
Oklahoma

Gentlemen:

RE: APPROVED APPLICATION NO. 32773

Enclosed find Approved Application No. 32773 . This is your authority to proceed with actual construction work which, under Sections 73-3-10 and 73-3-12, Utah Code Annotated, 1953, as amended, must be diligently prosecuted to completion. The water shall be put to beneficial use and proof of appropriation made to the State Engineer on or before ~~February 28, 1961~~ otherwise the application will lapse.

Failure on your part to comply with the requirements of the statutes may result in forfeiture of this application.

Yours truly,

Wayne D. Criddle

Wayne D. Criddle
STATE ENGINEER
STATE CAPITOL BUILDING
SALT LAKE CITY, UTAH

ADDRESS ALL COMMUNICATIONS TO:

js

Encl: Copy of approved application

APPLICATION APPROVED

NOTICE TO APPLICANT

The approval of this Application is not a certificate of change. It is merely your authority to begin construction work, which must be diligently prosecuted to completion. To secure a certificate of change under this Application proof of change must be submitted within the time limit allowed by the State Engineer. The amount of water for which certificate will be issued will depend upon the amount of water actually put to a beneficial use, not to exceed, however, the amount of water covered by the original right. For further information write the State Engineer.

RULES AND REGULATIONS

Applicants will save time and expense by familiarizing themselves with the law before making Applications.

If the reservoir is to be located on the channel of the source from which the water is to be appropriated, it should be so stated under explanatory, and—

1. The location of the impounding dam should be described in Paragraph 16.
2. The point where the released storage will be rediverted from the natural stream should be described under explanatory in accordance with the note under Paragraph 16.

When the water is to be stored in other than the natural channel of the source from which it is to be appropriated, it should be so stated under explanatory, and—

1. The point of diversion from the supplying source should be described in Paragraph 16.
2. The intersection of the longitudinal axis of impounding dam and centerline of stream channel or drainage and a similar point where the released storage will be rediverted from a natural channel should be described under explanatory in accordance with the note under Paragraph 16.

In all cases Paragraphs 17 to 27, incl., should describe the proposed diverting and carrying works, exclusive of natural channels, even if already constructed in whole or in part.

If it is proposed to collect the water of a number of springs or other sources at a common point, said point should be described as the point of collection in Paragraph 16, and the point of diversion from each source should also be described under explanatory in accordance with the note in Paragraph 16. The quantity of water sought from each source should be indicated under explanatory, the total equaling the quantity specified in Paragraphs 12 or 13. Where the source of supply is in reality a spring area, the point of diversion is the point where the water is collected; in such case the exterior boundary of the spring area must be described under explanatory by metes and bounds and located with reference to the same point as used in describing the point of collection and as outlined by the note under Paragraph 16.

No enlargement of an original water right may be made by a change Application, either as to quantity of water covered, period of use or otherwise.

When there are two or more coapplicants the Application must be accompanied by a power of attorney.

The applicant's permanent address should be given in Paragraph 2, and the State Engineer notified promptly of any change in address; otherwise applicant may lose rights initiated by Application by failing to receive notices sent from the State Engineer's office.

No Application or other paper pertaining to an Application will be marked received unless accompanied with the required filing fee.

Applications accepted and numbered by the State Engineer, when returned to applicant for correction or additions, must be amended with red ink. Erasures must not be made, but any matter may be eliminated by running a red line through it. Corrected Applications must be resubmitted to the State Engineer's office, within sixty days from the date of State Engineer's letter returning Application for correction; otherwise the priority of the right to change will be brought down to date corrected Application is resubmitted.

Applicants will be informed by the State Engineer's office when cost of publishing notice of Application is due, and must advance cost within sixty days after date of notice, otherwise Application will lapse.

Fees Required by Law Payable to State Engineer

For examining and filing Applications for change of point of diversion, place and nature of use.....	\$2.50
For approving and recording Applications for change of point of diversion, place and nature of use.....	\$2.50
For filing written proof of change.....	\$1.00
For examining maps, profiles and drawings that are part of the proof of change.....	\$5.00
For issuing certificate of change.....	\$1.00

NOTE—In addition to the above fees applicants must pay the cost of publication of "Notice to Water Users" concerning the proposed change.

20. The length of the diverting channel, exclusive of laterals, will be 15,000 feet
(If an existing channel is used give only the length of that part used under this Application)
21. The top width of the diverting channel will be (if a ditch) XX feet
22. The bottom width of the diverting channel will be (if a ditch) XX feet
23. The depth of water in the diverting channel will be (if a ditch) XX feet
24. The width of diverting channel will be (if a flume) XX feet
25. The depth of water in the diverting channel will be (if a flume) XX feet
26. The diameter of the diverting channel will be (if a pipe) 4.25 inches inches
27. The grade of the diverting channel will be 2.4 feet per thousand
28. The point at which it is proposed to return the water is situated (See note under 16) XX

29. The water is to be used for the same purposes as specified in the
original Application No. 32773

Total XX acres.

NOTE—If for irrigation, give legal subdivisions of land to be irrigated. If for other purposes, give place and extent of proposed use. If for power give number, size and make of wheels, head under which they will operate, total H. P. to be developed and place where power will be used.

30. The character of the soil to be irrigated is XX; subsoil XX

NOTE—Number 30 is to be filled in only when proposed change is for irrigation.

31. If paragraph 12 designates that only part of the right described in paragraph 1 to 11 inclusive is to be changed, designate the status of the water so affected by this change as to its being abandoned or used as heretofore.

EXPLANATORY

NOTE—Paragraph 13 on page 1 must not be used except when storage is contemplated; in such case Paragraph 14 should indicate the time in each year during which the water will be released and used. The lands to be inundated by the reservoir must be described in the space below this note as nearly as may be and by government subdivisions if upon surveyed land, and the area of the reservoir when at full stage should be given in acres; the height of the impounding dam must also be specified.

The following additional facts are set forth in order to define more clearly the full purpose of the proposed change:

The original Application No. 32773 specified points of diversion situate in Section 5, T. 41S., R. 24E., San Juan County, Utah, and bears the following notation: "Diversion will be from one or more or all of the above diversion points. Water from the several diversion points will be commingled in conveyance works or in use. The applicant proposes to divert water from the San Juan River partly or wholly by means of infiltration wells, pits or horizontal galleries, dug in the alluvial fill within the stream valley. The exact number, depth, diameter, spacing and yield of such wells, pits or galleries will be determined during the project construction; however, the aggregate withdrawal rate will not exceed that specified." The purpose of this Change Application is to secure approval of additional alternative points of diversion as hereinafter specified without waiver of any rights under the original Application and without increase in the quantity of water applied for or the ultimate objective and purpose of the original Application.

See "Explanatory" continued on attached sheet.

PHILLIPS PETROLEUM COMPANY

Signature of Applicant.

BY

Vice-President of Production

EXPLANATORY - contd. from printed form.

The additional alternative points of diversion from the source are in Section 3, T. 41S., R. 24E., San Juan County, Utah, situate at points as follows:

<u>Diversion Point</u>	<u>From West Line</u>	<u>From North Line</u>	<u>Subdivision</u>
1	100'	1780'	SW $\frac{1}{2}$ NW $\frac{1}{2}$
2	365'	1780'	"
3	630'	1770'	"
4	900'	1620'	"
5	1170'	1620'	"
6	1400'	1600'	SE $\frac{1}{2}$ NW $\frac{1}{2}$
7	1530'	1600'	"
8	1900'	1600'	"
9	2150'	1620'	"
10	2400'	1700'	"
11	2640'	1750'	"
12	2900'	1810'	SW $\frac{1}{2}$ NE $\frac{1}{2}$
13	3180'	1900'	"
14	3400'	1950'	"
15	3650'	2050'	"
16	3870'	2225'	"
17	4100'	2450'	SE $\frac{1}{2}$ NE $\frac{1}{2}$
18	4250'	2700'	NE $\frac{1}{2}$ SE $\frac{1}{2}$
19	4380'	2975'	"
20	4420'	3250'	"

10/13/61
October 13, 1961

AIRMAIL

Mr. Clair M. Senior
Senior & Senior
Attorneys at Law
10 Exchange Place
Salt Lake City, Utah

Re: Alternate or Additional Source of Water
for the Ratherford Unit, San Juan County, Utah

Dear Clair:

Herewith in triplicate is completed and signed application to the Utah State Engineer for additional and alternate points of diversion for water for water-flood purposes in the Ratherford Unit. I would appreciate it if you would handle this matter with the Water Engineer and, as diplomatically as possible, urge upon him the importance of expediting the matter as much as possible.

Having gotten these papers back from the Production Department too late to get a check for the filing fee, I would ask that you advance the fee and, upon being billed, I will send you the check.

If you need any additional information, please advise.

Very truly yours,

RMW:jd
Enclosures

R. M. Williams

cc - Mr. Shofner Smith ✓

Application for Permanent Change of Point of Diversion, Place and Nature of Use of Water STATE OF UTAH

Do not fill out this blank until you have read carefully and thoroughly understand the "Rules and Regulations" on the back hereof and all the notes in the body of it.

For the purpose of obtaining permission to permanently change the point of diversion, ~~place or nature of use of~~ (Strike out written matter not needed)

water right acquired by original Application No. 32773
(Give No. of Application, certificate of appropriation, title and date of Decree or other identification of right)
to that hereinafter described, application is hereby made to the State Engineer, based upon the following showing of facts, submitted in accordance with the requirements of the Laws of Utah.

1. The name of the applicant is Phillips Petroleum Company
2. The post-office address of the applicant is Bartlesville, Oklahoma
3. †The flow of water which ~~has been or~~ was to have been used in second-feet is 8
XX
4. †The quantity of water which has been or was to have been used in acre-feet is XX
5. †The water ~~has been or~~ was to have been used each year from January 1 to December 31 incl.
(Month) (Day) (Month) (Day)
6. †The water has been or was to have been stored each year from XX to XX incl.
(Month) (Day) (Month) (Day)
7. The drainage area to which source of supply belongs is (Leave blank)
8. The direct source of supply is Underground water and subsurface flow of San Juan River
in San Juan County.
9. †The point of diversion as described in the original Application ~~or the point at which the water has been diverted if~~ ^{are} situated at a point s in Section 5, T. 41S., R. 24E as more parti-
cularly set out in the original Application No. 32773.

10. †The water involved ~~has been or~~ was to have been used for the following purposes:
Pressure maintenance and secondary recovery purposes

Total XX Acres.

NOTE—If for irrigation, give legal subdivision of land and total acreage which has been or was to have been irrigated. If for other purposes, give nature, place and extent of use or proposed use.

11. †The point at which water has been or was to have been returned to the stream channel is situated as follows: XX

NOTE—The above space is to be filled in only when all or part of the water is returned to the natural stream or channel.

The Following Changes Are Proposed

12. The flow of water to be changed in cubic feet per second is No change
13. The quantity of water to be changed in acre-feet is XX
14. The water will be used each year from January 1 to December 31 incl.
(Month) (Day) (Month) (Day)
15. The water will be stored each year from XX to XX incl.
(Month) (Day) (Month) (Day)
16. The point at which it is now proposed to divert the water is situated (See note) See explanatory

NOTE—The "point of diversion," or "point of return," must be located by course and distance or by rectangular distances with reference to some regularly established United States land corner or United States mineral monument if within a distance of six miles of either, or if a greater distance, to some prominent and permanent natural object.

17. The proposed diverting and conveying works will consist of wells and conveyance pipe as explained in original Application No. 32773

18. The cross-section of the diverting channel will be. XXXXXXXXXX O
(Strike out ones not needed)

19. The nature of the diverting channel will be: earth, wood, iron, concrete.
(Strike out the ones not needed)

†Strike out written matter not needed.



Copied for
C. M. Boles
11-3-61 SS:mll

THE STATE OF UTAH
OFFICE OF STATE ENGINEER

WAYNE D. CRIDDLE
STATE ENGINEER

SALT LAKE CITY
October 30, 1961

Issue Date: October 30, 1961
Expiration Date: April 30, 1962

Phillips Petroleum Company
c/o Senior and Senior, Attorneys
#10 Exchange Place
Salt Lake City 11, Utah

Gentlemen:

RE: APPROVED APPLICATION NO. 32773 AND
CHANGE APPLICATION NO. a-4025

This is to acknowledge receipt of your Permanent Change Application No. a-4025, which proposes to change the point of diversion of 8.0 sec.-ft. of water initiated by Application No. 32773. The water was to have been diverted from ten 12.75-inch O.D. wells located within S $\frac{1}{2}$ N $\frac{1}{2}$ NE $\frac{1}{4}$ and SE $\frac{1}{4}$ NE $\frac{1}{4}$ of Sec. 5, T41S, R24E, SLB&M. It is now proposed to divert the 8.0 sec.-ft. of water from a total of eleven 12.75 inches O.D. wells, between 35 and 50 ft. deep, ten of these being the same as heretofore described and thirty-one wells to be located within NW $\frac{1}{4}$ Sec. 3, S $\frac{1}{2}$ Sec. 4, NW $\frac{1}{4}$ Sec. 5, T41S, R24E, SLB&M. The water is to be used for pressure maintenance and secondary recovery purposes as heretofore.

You have requested permission to proceed immediately with the drilling of these additional 31 wells. This letter grants you that privilege with the understanding that all risks as regards water rights are being assumed by you.

If other than new standard casing is to be used in these wells, such casing must be inspected and approved by a representative from this office. All wells must be so constructed and finished that they may be readily controlled at all times, in order to prevent waste of underground water. Wells must be drilled and cased in such a manner that will prevent the infiltration of contaminated water into them.

The driller must be bonded and have a current permit from the State Engineer. Before commencing, he must give this office notice as to the day he will begin drilling. Also, within 30 days after the well has been completed or abandoned, he must file a well driller's report for each well. These reports are to contain accurate and complete information regarding the work done and become part of the files in this office pertaining to the above-numbered wells.

This is permission for a licensed driller to begin drilling your wells.

Please note that the expiration date of this letter is April 30, 1962.

Yours truly,

Wayne D. Criddle
Wayne D. Criddle
STATE ENGINEER

RECEIVED

ds

1961

SENIOR

APPLICATION TO APPROPRIATE WATER STATE OF UTAH

NOTE:—The information given in the following blanks should be free from explanatory matter, but when necessary, a complete supplementary statement should be made on the following page under the heading "Explanatory."

For the purpose of acquiring the right to use a portion of the unappropriated water of the State of Utah, for uses indicated by (X) in the proper box or boxes, application is hereby made to the State Engineer, based upon the following showing of facts, submitted in accordance with the requirements of the Laws of Utah.

1. Irrigation ☐ Domestic ☐ Stockwatering ☐ Municipal ☐ Power ☐ Mining ☒ Other Uses ☐

2. The name of the applicant is PHILLIPS PETROLEUM COMPANY

3. The Post Office address of the applicant is Bartlesville, Oklahoma

4. The quantity of water to be appropriated is -- 8 -- second-feet or acre-feet

5. The water is to be used for See Explanatory from January 1 to December 31
(Major Purpose) (Month) (Day) (Month) (Day)

other use period from to
(Minor Purpose) (Month) (Day) (Month) (Day)

and stored each year (if stored) from to
(Month) (Day) (Month) (Day)

6. The drainage area to which the direct source of supply belongs is (Leave Blank)

7. The direct source of supply is Underground water and subsurface flow of San Juan River
(Name of stream or other source)

which is tributary to Colorado River tributary to

*Note.—Where water is to be diverted from a well, a tunnel, or drain, the source should be designated as "Underground Water" in the first space and the remaining spaces should be left blank. If the source is a stream, a spring, a spring area, or a drain, so indicate in the first space, giving its name, if named, and in the remaining spaces, designate the stream channels to which it is tributary, even though the water may sink, evaporate, or be diverted before reaching said channels. If water from a spring flows in a natural surface channel before being diverted, the direct source should be designated as a stream and not a spring.

8. The point of diversion from the source is in San Juan County, situated at a point*

See Explanatory #1-S.1000 ft. and W. 150 ft.; #2-S.1000 ft. and W. 450 ft.;
#3-S.1000 ft. and W. 750 ft.; #4-S.1000 ft. and W. 1050 ft.; #5-S.1000 ft. and
W. 1350 ft.; #6-S.1000 ft. and W. 1650 ft.; #7-S.1000 ft. and W. 1950 ft.;
#8-S.1000 ft. and W. 2250 ft.; #9-S.1000 ft. and W. 2550 ft.; and #10-S.1000 ft. and
W. 2850 ft.; all from NE Cor. Sec. 5, T15S, R24E, S10&M. (See letter of 7-16-37 attached)

*Note.—The point of diversion must be located definitely by course and distance or by giving the distances north of south, and east or west with reference to a United States land survey corner or United States mineral monument, if within a distance of six miles of either, or if at a greater distance, to some prominent and permanent natural object. No application will be received for filing in which the point of diversion is not defined definitely.

9. The diverting and carrying works will consist of See Explanatory

10. If water is to be stored, give capacity of reservoir in acre-feet height of dam
area inundated in acres legal subdivision of area inundated

11. If application is for irrigation purposes, the legal subdivisions of the area irrigated are as follows:

 Total Acres

12. Is the land owned by the applicant? Yes No

13. Is this water to be used supplementally with other water rights? Yes No

If "yes," identify other water rights under explanatory.

14. If application is for power purposes, describe type of plant, size and rated capacity.

15. If application is for mining, the water will be used in Greater Aneth Area
oil field where the following ores are mined oil and gas

16. If application is for stockwatering purposes, number and kind of stock watered

17. If application is for domestic purposes, number of families to be served

18. If application is for municipal purposes, name of municipality

19. If application is for other uses, include general description of proposed uses

20. Give place of use by legal subdivision of the United States Land Survey for all uses described in paragraphs 14 to 19, incl. See Explanatory

21. The use of water as set forth in this application will consume -- 8 -- second-feet of water
and -- 0 -- second feet will be returned to the natural stream or source at a point described
as follows:

EXPLANATORY

The following additional facts are set forth in order to define more clearly the full purpose of the proposed application:

ITEM 2

The water will be pumped from the diversion area to the oil field where the water will be injected under pressure through deep wells into the petroleum-bearing formations for pressure maintenance and secondary recovery purposes.

ITEM 3

The point or points of diversion from the source will be in Section 5, T41S, R24E SIM, San Juan County, situated as follows: From that point at which the south bank of the river channel intersects the east line of Section 5, T41S, R24E, to that point at which the South bank of river channel intersects the North line of Section 5, T41S, R24E.

Diversion will be from one or more wells or infiltration galleries to be drilled in the alluvial fill and to be located as close to the South bank of the river channel as is practical within the east-west limits as above defined. Specific location and number of diversion points will be determined by a hydrographic survey and/or producing characteristics of wells to be drilled. The aggregate withdrawal, the rate of which is not to exceed that specified in this application, will be commingled in a conveyance works described in greater detail herein.

ITEM 9

The diverting and carrying works will consist of 12-1/4" diameter wells, cased with 35 to 50 feet of 8-5/8 inch outside diameter pipe to be drilled to depths of from 35 feet to 50 feet and about 1,000 feet of 10-3/4 inch conveyance pipe to places of use.

ITEM 20

Township 41 South, Range 23 East, SIM

S/2 Sec. 1; SE/4 Sec. 2; E/2 Sec. 11; All Sec. 12; All Sec. 13, E/2 Sec. 14, NE/4 Sec. 24.

Township 41 South, Range 24 East, SIM

All Sections 3, 4, 5, 6, 7, 8, 9, 10; W/2 Sec. 11, W/2 Sec. 14; All Sections 15, 16, 17, 18, 19, 20, 21; NW/4, W/2 SW/4 Sec. 22; W/2 NE/4, NW/4, W/2 SW/4 Sec. 28; All Sections 29, 30; N/2 Sec. 31; N/2 Sec. 32.

Said described lands, which are in San Juan County, Utah, constitute the Ratherford portion of the Greater Aneth Area oil field.

Continued on page 4

(Use page 4 if additional explanatory is needed.)

The quantity of water sought to be appropriated is limited to that which can be beneficially used for the purpose herein described.

PHILLIPS PETROLEUM COMPANY

By: *L. E. Fitzgerald*

Signature of Applicant

VICE PRESIDENT OF PRODUCTION

*If applicant is a corporation or other organization, signature must be the name of such corporation or organization by its proper officer, or in the name of the partnership by one of the partners, and the names of the other partners shall be listed. If a corporation or partnership, the affidavit below need not be filled in. If there is more than one applicant, a power of attorney, authorizing one to act for all, should accompany the Application.

DECLARATION OF CITIZENSHIP

STATE OF UTAH,
County of..... } ss

On the day of 19..... personally appeared before me, a notary public for the State of Utah, the above applicant who, on oath, declared that he is a citizen of the United States, or has declared his intention to become such a citizen.


My commission expires:

(SEAL)

Notary Public

FEES FOR APPLICATIONS TO APPROPRIATE WATER IN UTAH

Flow rate — c.f.s.		Cost
0.0	to 0.1	\$ 10.00
over 0.1	to 0.5	20.00
over 0.5	to 1.0	30.00
over 1.0	to 15.0	30.00 plus \$5/cfs above 1.00 cfs.
over 15.0		100.00
Storage — acre-feet		
0	to 20	15.00
over 20	to 500	30.00
over 500	to 7500	30.00 plus \$5/500 a. f. above first 500
over 7500		100.00



(This section is not to be filled in by applicant)

STATE ENGINEER'S ENDORSEMENTS

1. Feb. 27, 1961 Application received by mail over counter in State Engineer's office by ...
2. ... Priority of Application brought down to, on account of ...
3. Feb. 27, 1961 Application fee, \$ 5.50, received by ... Rec. No. 022365
4. Mar. 10, 1961 Application copied in book 711.32 page 357, and indexed by ...
5. ... Application platted by ... aac-(6)ab4-(6)ab4-(7)ab4-(1)abc-(1)abc-(6)ab4
6. April 7, 1961 Application examined by ME
7. ... Application returned, ... or corrected by office ...
8. ... Corrected Application resubmitted over counter by mail to State Engineer's office.
9. April 7, 1961 Application approved for advertisement by ...
10. June 16, 1961 Notice to water users prepared by P. K. H.
11. June 29, 1961 Publication began; was completed July 13, 1961
Notice published in San Juan Record, Monticello, Utah
12. June 27, 1961 Proof slips checked by ...
13. ... Application protested by ...
14. July 25, 1961 Subscriber paid \$22.10/6
Hearing held by ...
15. ... Field examination by ...
16. Sept 5, 1961 Application designated for approval rejection ...
17. Sept. 11, 1961 Application copied or photostated by T.E. proofread by ...
18. Sept. 11, 1961 Application approved rejected
19. Conditions:
This Application is approved, subject to prior rights, as follows:
a. Actual construction work shall be diligently prosecuted to completion.
b. Proof of Appropriation shall be submitted to the State Engineer's office by Feb. 28, 1963
c. ...
20. ... Time for making Proof of Appropriation extended to ...
21. ... Proof of Appropriation submitted.
22. ... Certificate of Appropriation, No. ..., issued ...

Wayne D. Criddle
Wayne D. Criddle State Engineer

EXPLANATORY CONTINUED

The use of the applied for water for the planned pressure maintenance and secondary recovery operations will permit the recovery of substantial quantities of oil and gas which would otherwise not be recovered.

NOTICE TO APPLICANT

All waters in this state, whether above or under the ground, are the property of the public, subject to all existing rights to the use thereof. No appropriation of the unappropriated public water may be made and no rights to the use thereof shall be recognized except Application for such appropriation first be made to the State Engineer.

The approval of this Application is not a Certificate of Appropriation. It is merely your authority to begin construction work, which must be prosecuted diligently to completion. To secure a Certificate of Appropriation under this Application, Proof of Appropriation must be submitted within the time limit allowed by the State Engineer. The amount of water for which Certificate will be issued will depend upon the amount of water actually put to a beneficial use, not to exceed, however, the amount of water specified in this Application. Proof of Appropriation must be made in accordance with the requirements of the law. For further information write the State Engineer.

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☒GAS
WELL ☐

OTHER

SINGLE
ZONE ☐MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

Phillips Oil Company

3. ADDRESS OF OPERATOR

P. O. Box 2920 Casper, WY 82602

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface

660' FNL, 660' FWL (NW NW)

At proposed prod. zone

same

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

Approximately 4 miles south of Montezuma Creek, Utah

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drig. unit line, if any)

660' East of Ratherford Unit

Lease Line

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.

1200' West

of 19W21

16. NO. OF ACRES IN LEASE

2560 Acres

19. PROPOSED DEPTH

5700'

17. NO. OF ACRES ASSIGNED TO THIS WELL

40 Acres

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

4708' ungraded ground

22. APPROX. DATE WORK WILL START*

November 1984

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
17-1/2"	13-3/8"	48#	100'	150 sx (Circ to surface)
12-1/4"	9-5/8"	36#	1600'	600 sx (Circ to surface)
8-3/4"	7"	23# & 26#	5700'	1000 sx (T.O.C. Approx 2000')

Approval is requested to drill Ratherford Unit #19-11, a Desert Creek Development oil well, to increase the ultimate recovery from the Ratherford Unit.

BOP equipment will be operated daily and tested weekly.

RECEIVED

SEP 27 1984

DIVISION OF OIL
GAS & MININGAPPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

DATE: 10/10/84

BY: [Signature]

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

A. E. STUART

TITLE

Area Manager

DATE

September 18, 1984

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY


TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

*See Instructions On Reverse Side


COMPANY PHILLIPS OIL COMPANY
LEASE RATHERFORD UNIT WELL NO. 19-11
SEC. 19, T. 41S R. 24E
SAN JUAN COUNTY, UTAH
LOCATION 660' FNL 660' FWL
ELEVATION 4708 ungraded ground



SCALE—4 INCHES EQUALS 1 MILE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM
FIELD NOTE OF ACTUAL SURVEYS MADE BY ME UNDER MY SUPER-
VISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF.

SEAL:



SURVEYED May 16 19 84

FARMINGTON, N. M.

RATHERFORD UNIT #19-11

Supplement to Form 9-331C "Application for Permit to Drill, Deepen, or Plug Back."

DRILLING PROGRAM

1. Surface formation is the Dune Sand, which consists of loose windblown sand, age-recent.

Estimated tops of geologic markers:

Chinle	1425'
Shinarump	2240'
DeChelly	2555'
Hermosa	4435'
Desert Creek Zone I	5435'

2. Brackish water-bearing sands are expected in the Navajo, Wingate, and DeChelly formations. Oil is expected to be encountered in the Ismay and Desert Creek formations. The top of cement will be approximately at 2000'.

3. Blow-out preventers will be 10" Series 900 equipment to be tested initially to 3000 psi. They will be inspected and operated daily and pressure tested weekly to 1500 psi. Weekly pressure tests will be supervised by representatives of Phillips Oil Company and the drilling contractor. Tests will be recorded on the daily drilling report which will remain on the rig floor during drilling operations. BOP tests will be conducted in accordance with Phillips standards, copy attached.

4. a. Proposed Casing Program:

1. Conductor casing:

100'	13-3/8"	48#/ft	H-40	ST&C	new
------	---------	--------	------	------	-----

2. Surface casing:

1600'	9-5/8"	36#/ft	K-55	ST&C	new
-------	--------	--------	------	------	-----

Surface casing will be tested to 1500# before drilling out.

3. Production casing:

5700'	7"	23# & 26#/ft	K-55	ST&C	new
-------	----	--------------	------	------	-----

Production casing will be tested to 3000#.

b. Proposed Cementing Program:

1. Conductor Casing:

Conductor casing will be cemented with 150 sks Class B cement. Cement will be brought to surface.

2. Surface Casing:

Surface casing will be cemented with 300 sks "light" cement followed with 300 sks Class B cement. Cement will be brought to surface.

3. Production casing:

Production casing will be cemented with "light" cement followed with Class B cement. For cement volume, caliper will be used with 15% excess. The top of the cement should be around 2000'. If other zones with hydrocarbon potential are encountered, they will be covered with cement.

c. Auxiliary Equipment:

Auxiliary equipment will include upper and lower kelly cocks, a drill string safety valve, and a pit level indicator.

5. Drilling Fluid:

Drilling fluid will be a fresh water based mud system. Spud mud is gel and water with a weight of 8.4-8.8 ppg. From the surface to approximately 1600', gel and water will be used. Mud weight may be up to 9 ppg to control water flow from the Wingate formation. A slurry of 8.6-9.5 ppg, 32-38 viscosity, and less than 15cc/30 min. water loss will be used from 1600'-5200'. Mud weight may be increased to 10.4 ppg if a water flow is encountered. From 5200' to total depth mud properties will be 10.5-12.5 ppg, 40-45 viscosity, and below 10 cc water loss.

Adequate quantities of mud materials will be stored at the location to equal the volume of the rigs complete circulating system. A flow sensor will be used.

6. Testing, logging, and coring:

The logging program will consist of DLL, GR, SP, and Caliper from T. D. to the surface casing. A FDC/CNL and a Micro-proximity log will be run from T. D. to 4300'. A temperature or cement bond log will be run to determine cement top. It is proposed to core the Desert Creek Zone I.

7. Downhole Conditions:

Drilling in the area indicates no abnormal pressures, temperatures, or hydrogen sulfide gas.

8. Phillips anticipates starting operations in November 1984.
Drilling operations are estimated to take fifteen days per well.

CULTURAL RESOURCE REPORT

San Juan College has prepared a cultural resource inventory of the subject wellsite. A copy of the report has been sent to the BLM Farmington office. Pertinent information regarding the subject well is attached.

SURFACE USE PROGRAM

1. Existing Roads

- a. Access to existing lease roads is approximately 4 miles south of Montezuma Creek, Utah.
- b. The existing roads will be maintained in the same or better condition.
- c. Refer to the attached access road map for road information.

2. Access Roads

Planned upgrading of existing access roads is shown on the attached map.

3. Location of Existing Wells.

Locations of existing wells are shown on the attached maps.

4. Production from the proposed well will be piped to Ratherford Unit Tank Battery #1, located in the SW SW Sec. 16-T41S-R24E San Juan County, Utah. The flowline will be visible from the existing lease roads. A plat of the proposed leadline is attached.

5. Water Supply

- a. The source of water to drill the subject well is from the River Booster, NE/4 Sec. 5., or from the Water Injection Plant, SE/4 Sec. 17 in T41S-R24E, San Juan County, Utah.
- b. The drilling water will be trucked from the water source to the subject well.
- c. A water supply well will not be drilled on the lease.

6. Construction Materials

- a. Only native soils will be used for construction of wellsite and the access road.

- b. Pit run rock will be used on the wellsite and access road when needed.
- c. The above materials are owned by the Navajo Tribe.

7. Waste Disposal

- a. Cuttings: Cuttings will be contained in a fenced lined reserve pit until dry enough to cover. Upon abandonment, the reserve pit area will be backfilled, shaped to natural topography, and seeded.
- b. Drilling Fluid: Drilling fluid will be contained in a fenced lined reserve pit until dry enough to cover. Upon abandonment, the reserve pit area will be backfilled, shaped to natural topography, and seeded.
- c. Garbage/Trash: All garbage and trash will be put in the burn pit. The burn pit will be fenced on four sides. After the burn pit is no longer in use, the trash and garbage will be covered with a minimum of 4 feet of fill.
- d. Salt: No salts are anticipated on this well. If salt is present, it will be disposed of in the reserve pit.
- e. Chemicals: Chemicals will be disposed of in the reserve pit.
- f. Sewage: Dry chemical toilets will be used.

8. Ancillary Facilities

No ancillary facilities are required.

9. Well Site Layout.

- a. Refer to attached Rig Layout plat
- b. The reserve pit will be lined with a non-porous material.

10. Surface Reclamation Plans

- a. Construction Program: A cross section of the drill site showing cuts and fills is attached.
- b. Well Abandonment: All disturbed areas will be shaped to the natural topography and seeded in accordance with BLM requirements.
- c. Producing Well: Those areas not needed for production purposes will be recontoured to the surrounding topography. Seeding will be in accordance with BLM requirements.

- d. Pipelines and flowlines: Flowlines will be above ground and follow existing roads.
- e. Rehabilitation will begin as soon as possible, considering weather and other factors, and proceed per recommendation of the BLM. The reserve pit will be reclaimed once it dries.

11. Surface Ownership: The wellsite location, access road and leadline are on the Navajo Indian Reservation. No dwellings are in the proposed drilling area.

12. Other information:

The reserve pit will be fenced on three sides during drilling and on the fourth side after the rig is moved out.

13. Operator's Representative and Certification.

a. Field Representative:

A. E. Stuart
P. O. Box 2920
Casper, Wyoming 82602
307-237-3791

I hereby certify that I or persons under my direct supervision have inspected the proposed drill site and access route; and I am familiar with the conditions which currently exist; that the statements made in this plan are to the best of my knowledge true and correct; and that the work associated with operations proposed herein will be performed by Phillips Oil Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.


Date

9/24/84


A. E. Stuart
Area Manager

BJM/fb (18)
Casper - RC



Profile for
 PHILLIPS OIL COMPANY #19-11 RATHERFORD UNIT
 660'FNL 660'FWL Sec. 19-T11S-R24E
 SAN JUAN COUNTY, UTAH



Scale: 1"=50'


The reserve pit dimensions
 will be changed to 60'x250'

B.M.
 BJM
 9-18-84



WHITE MESA VILLAGE QUADRANGLE
UTAH
15 MINUTE SERIES (TOPOGRAPHIC)





CAJON MESA



Vicinity Map for
PHILLIPS OIL COMPANY #19-11 RATHERFORD UNIT
660'FNL 660'FWL Sec. 19-T41S-R24E
SAN JUAN COUNTY, UTAH

RATHE FORD UNIT # 19-11


NW NW SEC. 19 T41S-R24E




1. RESERVE PIT
2. TRASH PIT
3. CIR. PITS & PUMP
4. RIG
5. CAT WALK & PIPE RACKS
6. TRAILERS

DRILLING RIG LAYOUT


OUTLINE OF LOCATION APPROXIMATELY 260' x 350'.
NOT TO SCALE.




NO.	REVISION	BY	DATE	CHKD	APP'D	
FOR BIDS	<div style="display: flex; align-items: center; justify-content: center;"> <div> PHILLIPS PETROLEUM COMPANY BARTLESVILLE, OKLAHOMA </div> </div>	JA NO.		FILE CODE		
FOR APPR		AFE NO.		SCALE 2.2"=1 mi		
FOR CONST		<div style="text-align: center;"> RATHERFORD UNIT WELL 19-11 PROPOSED NW NW SEC. 19 T41S-R24E SAN JUAN CO., UTAH </div>				
DRAWN 7-20-84/BJM	DWG NO.					
CHECKED	SH NO.					
APP'D						





1. Relocation of proposed road		BJM	8-15-84		
NO.	REVISION	BY	DATE	CHKD	APPD
FOR BIDS	PHILLIPS PETROLEUM COMPANY		JA NO.	FILE CODE	
FOR APPR	BARTLESVILLE, OKLAHOMA		AFE NO.	SCALE 2.2" = 1 mi	
FOR CONST	RATHERFORD UNIT WELL 19-11		DWG NO.		
DRAWN 7-20-84 BJM	PROPOSED ROAD PLAT		SH NO.		
CHECKED	NW NW SEC. 19 T41S-R24E				
APP'D	SAN JUAN CO., UTAH				



1		Relocation of proposed leadline		BY	8-15-84	CHKD	APP'D
NO.		REVISION					
FOR BIDS		PHILLIPS PETROLEUM COMPANY		JA NO.		FILE CODE	
FOR APPR		BARTLESVILLE, OKLAHOMA		AFE NO.		SCALE 2.2"=1 mi	
FOR CONST		RATHERFORD UNIT WELL 19-11 PROPOSED LEADLINE PLAT NW NW SEC. 19 T41S-R24E SAN JUAN CO., UTAH		DWG NO.			
DRAWN 7-20-84 BJM				SH NO.			
CHECKED							
APP'D							



NO.	REVISION	BY	DATE	CHKD	APP'D
FOR BIDS	 PHILLIPS PETROLEUM COMPANY 			JA NO.	FILE CODE
FOR APPR	BARTLESVILLE, OKLAHOMA			AFE NO.	SCALE 2.2"=1 mi
FOR CONST	RATHERFORD UNIT WELL 19-11 INJECTION LINES NW NW SEC. 19 T41S-R24E SAN JUAN CO., UTAH			DWG NO.	
DRAWN 7-20-84/BJM				SH NO.	
CHECKED					
APP'D					




Figure 7-10. Standard Hydraulic Blowout Preventer Assembly
(2 M or 3 M Working Pressure) Alternative 3 (without Drilling Spool)

Well Control 4
January/83

PHILLIPS PETROLEUM COMPANY



Page 251
Section II

FIELD PRACTICES AND STANDARDS

7.6 Testing Surface Blowout Preventer Equipment

7.6.1 Pressure Test Frequency

All rams, annulars, valves, choke and kill lines, choke manifold, kelly cocks, and safety valves shall be pressure tested at the following frequencies:

- (1) Initial installation of blowout preventers.
- (2) After setting casing, before drilling cement.
- (3) Every 7 days or on first trip out of hole after 7 days since previous pressure test.
- (4) After any component of the blowout preventer assembly is disturbed, replaced or repaired (this includes lines, valves, or choke manifold). In this case, the component changed may be the only component tested.
- (5) Prior to conducting first drill stem test in a series of one or more DST's.
- (6) Any time the Phillips Wellsite Supervisor deems necessary, such as prior to drilling into suspected high pressure zones.



7.6.2 Function Test Frequency

All rams, annulars, valves, and other items specified below, shall be function tested at the following frequencies.

- (1) On initial installation from driller control and remote panel.
- (2) Each trip out of hole alternating between driller's and remote control panel but not more than once every twenty-four (24) hours. Close pipe rams or annular preventer ONLY on drill pipe.

7.6.3 Test Pressures

Use the following table to identify which test is appropriate and at what pressure.

TEST	DESCRIPTION
Low Pressure	Test to 200-300 psi prior to each high pressure test.
Initial Installation	<p>Test all rams, annulars, valves, choke manifold, kelly cocks, and safety valves to the lesser of the following pressures.</p> <ul style="list-style-type: none"> . Rated working pressure of the component in the blowout preventer assembly with the exception of annular preventer which is to be tested to 70% of the rated working pressure. . The API rated casing burst pressure of the last casing to be utilized in the well with the BOP assembly being tested. . Rated working pressure of the casing head. . If "Cup Tester" is used do not exceed 80% of the API rated burst pressure of the casing.
Repair	Repaired or replaced components are to be tested to the same pressures used in the Initial Test.

FIELD PRACTICES AND STANDARDS

7.6.3, cont'd

TEST	DESCRIPTION
Weekly and After Setting Casing	<p>Test all rams, annulars, valves, choke and kill lines, choke manifold, kelly cocks, and safety valves, to the lesser of the following pressures.</p> <ul style="list-style-type: none">. 50% of the rated working pressure of the component to be tested.. 80% of the API rating of the casing burst pressure then in the well.. Test blind rams during internal casing pressure test. (Refer to drilling program for test pressures).
DST Operations	<p>Test all pipe rams, annular preventers, valves, choke and kill lines, choke manifold, kelly cocks, and safety valves to the maximum anticipated surface pressure expected while conducting drill stem tests. Do not test annular to more than 70% of its working pressure.</p>
Shallow Casing	<p>Where cased hole is less than 2000 feet measured depth, the test pressure may be 1.5 psi per foot of casing depth, not to exceed 80% of the API rated burst pressure. In the case of shallow conductor casing or drive pipe (500 feet or less) that is equipped with one BOP, then the test pressures do not need to exceed 1.0 psi per foot of casing depth.</p>
Accumulator	<p>Test accumulator to the manufacturer's rated working pressure. Test the accumulator for time to pump up to specifications.</p>

7.6.4 Blowout Preventer Test Practices

- (1) All pressure tests shall be witnessed by Phillips' Representative and the Contractor's Senior Supervisor on Location. All tests shall be recorded on the Phillips' Daily Drilling Report, the IADC Report and the BOP Test Form; see Figure 7-13. A reproducible copy of the BOP Test Form (Figure 7-13) can be found in Section III.



FIELD PRACTICES AND STANDARD

7.6.4, cont'd

- (2) Hold all low pressure tests for three minutes and high pressure tests for five minutes or until Phillips Representative and the Contractor's Senior Supervisor are satisfied no leaks exist.
- (3) A detail procedure for the testing of blowout preventer and choke manifold equipment will be included in the drilling programs. The procedure is to be distributed for each drilling unit under contract by the operating office. Each operating office must include the following practices:
 - a. Prior to testing, all lines and valves will be thoroughly flushed to ensure the system is clear. Test all opening and closing control lines to 1500 psi and inspect for leaks.
 - b. If necessary, run a stand of drill collars below the test plug to prevent unseating the test tool during testing.
 - c. All precautions must be taken to avoid pressuring the casing below the test tool.
 - d. The running string is to be full of water (or antifreeze solution) for immediate indication of test tool leakage.
 - e. All pipe rams, blind/shear rams, blind rams, annular preventers, valves, fail-safe valves, choke and kill lines are to be tested at the frequencies and pressures outlined in this section.
 - f. Drill pipe safety valve, lower and upper kelly cocks are to be tested from below at pressures and frequencies outlined in this section.
 - g. All test fluids are to be bled back to the pump unit in safe manner.

7.6.5 Testing Wellhead Pack-offs

The wellhead pack-off is to be pressure tested upon installation for five minutes. Test pressure is to be 80% API rated casing collapse or the rated working pressure of the casing head whichever is the lesser. Casing annulus valve(s) must be in open position to prevent casing collapse during pack-off testing.

When testing the wellhead pack-off, use recorded test pressures and volumes to determine if pack-off is leaking. Pressure should be immediately released at the first indication of a leak.

FIELD PRACTICES AND STANDARDS

7.6.6 Safety Precautions

One pumping unit operator is to be stationed at the high pressure pumping unit, and is to remain at this station until all testing has been completed. The pump unit operator is to be in continuous communication with the person who is recording the test data. The Phillips Wellsite Supervisor and Contractor's Senior Supervisor on location will be the only personnel who will go into the test area to inspect for leaks when the equipment involved is under pressure. The rig crews are to stay clear of the area until such time that both the Phillips Wellsite Supervisor and the Contractor's Senior Supervisor have contacted the pumping unit operator and all three have agreed that all pressure has been released, and there is no possibility of pressure being trapped. The rig crews may then go into the area to repair leaks or work as directed.

All lines, swings, and connections that are used in the testing of the blowout preventers are to be adequately secured in place.

Pressure is to be released only through the pressure release lines that are vented back into the pump unit tanks. The lines are to be clamped down to direct the flow into unit tanks.



Cultural Resources Management Program

San Juan College

Archaeological Surveys of
Six Proposed Well Locations and Associated Flow Lines and Access Routes
in San Juan County, Utah,
Conducted for Phillips Petroleum Company



Report 84-SJC-071B


Federal Antiquities Permit 83-AZ/NM/UT-047 and
Navajo Nation Antiquities Permit #1984-4

June 13, 1984

Phillips Petroleum Company - Ratherford Unit:

17-33
18-24
18-33
19-11
19-44
21-22

A Cultural Resources Inventory Prepared by Kristin Langenfeld,
Archaeologist, Under the Supervision of Dr. Richard P. Watson,
Director, Cultural Resources Management Program, San Juan College,
Farmington, New Mexico



Scale 1: 250,000

Report 84-SJC-071B

Project Location

ABSTRACT

On May 21, 22 and 23, 1984 a Class III Archaeological Survey was conducted south of Montezuma Creek, San Juan County, Utah on lands to be used for nineteen proposed well locations, associated access routes and flow lines. A total of eight archaeological sites and eleven isolated occurrences were located during the inspections. This report details the results of archaeological surveys on six of the proposed locations. Approximately 19 hectares (47 acres) in Sections 17, 18, 19 and 21 were inspected for cultural resources in conjunction with the project areas described in this report. A total of eight sites and five isolated occurrences were located. Three sites are undated lithic scatters, four sites are Anasazi manifestations ranging from Basketmaker II-Pueblo III, and one site is Recent Navajo with a possible prehistoric component. Recommendations for management include avoidance of sites by restrictions on pad size and mechanical disturbance (four sites) and archaeological monitoring (two sites). One site is outside the project area and no avoidance or further mitigation is necessary.

The work was conducted by the:

Cultural Resources Management Program
San Juan College
4601 College Blvd.
Farmington, NM 87401-4699
Phone: 505/326-3311, Extension 344

The work was conducted under:

Federal Antiquities Permit 83-AZ/NM/UT-047 and
Navajo Nation Antiquities Permit #1984-4

The work was conducted for:

Phillips Petroleum Company

TABLE OF CONTENTS

ABSTRACT	i.
LIST OF FIGURES	iii.
INTRODUCTION	1.
PHYSIOGRAPHY AND ENVIRONMENT	3.
RECORDS SEARCH	10.
PROJECT LOCATIONS	13.
DISCUSSION OF CULTURAL RESOURCES	35.
TABLE 1: Summary of Isolated Occurrences	36.
TABLE 2: Summary of Archaeological Sites	40.
SUMMARY OF RECOMMENDATIONS	41.
TABLE 3: Summary of Recommendations	42.
BIBLIOGRAPHY	43.
SITE FORMS = SJC-1104	44.
SJC-1105	49.
SJC-1106	55.
SJC-1107	60.
SJC-1108	65.
SJC-1109	70.
SJC-1110	75.
SJC-1111	80.

LIST OF FIGURES

FIGURE 1: General Location of Project Area	4.
FIGURE 2: Project Area Showing Proposed Well Locations and Archaeological Sites	5.
FIGURE 3: Vicinity Map Showing Locations of Nearby Sites (FOR B.I.A. ARCHAEOLOGIST ONLY)	12a.
FIGURE 4: Project Locations - Section 17	15.
FIGURE 5: Project Locations - Section 18	22.
FIGURE 6: Project Locations - Section 19	29.
FIGURE 7: Project Locations - Section 21	34.
FIGURE 8: Site SJC-1104	48.
FIGURE 9: Site SJC-1105	54.
FIGURE 10: Site SJC-1106	59.
FIGURE 11: Site SJC-1107	64.
FIGURE 12: Site SJC-1108	69.
FIGURE 13: Site SJC-1109	74.
FIGURE 14: Site SJC-1110	79.
FIGURE 15: Site SJC-1111	84.

INTRODUCTION

On May 21, 22, and 23, 1984 Kristin Langenfeld and L. Jean Hooton, from the Cultural Resources Management Program, San Juan College, conducted a Class III Archaeological Survey for Phillips Petroleum Company. The survey was conducted under Federal Antiquities Permit 83-AZ/NM/UT-047 and Navajo Nation Antiquities Permit #1984-4 on lands owned by the Navajo Nation. Mr. Max Isaacs, of Phillips Petroleum Company, accompanied the archaeologists during the inspection.

Nature of Proposed Land Modifications

Land modifications proposed by Phillips Petroleum for the Ratherford Unit include the construction of well locations and, in some cases, access routes. These activities will constitute the major mechanical disturbances in the area. In addition, aboveground flow lines connecting each well with a local gathering station will be laid. These lines usually parallel either existing or proposed roads and will be laid from the road. Mechanical disturbance connected with flow lines will be minimal. Access routes, where required, will either follow existing two-tracks or run cross-country. In a few cases existing, bladed roads will be modified to accommodate drill rigs. Well locations will be 350 feet x 350 feet (107 meters x 107 meters), including pits. Access routes will be 30 feet (10 meters) in width and flow lines will require a 10-foot-wide (3-meter) corridor. Combined flow lines and access routes will require a 40-foot (12-meter) right-of-way.

Methodology

A series of parallel transects spaced 10 to 15 meters apart was used to survey a 450-foot x 450-foot (137-meter x 137-meter) area for each well location. This includes a buffer zone of 50 feet (15 meters) around the perimeter of the project area.

Zigzag transects were used to survey 25-foot-wide (7.6-meter) flow line corridors. This includes a buffer zone of 7.5 feet (2.3 meters) on each side of the right-of-way. Zigzag transects were used to survey 75-foot-wide (23-meter) access or combined access and flow line routes. This includes a buffer zone of between 17.5 feet (5 meters) and 23 feet (7 meters) on each side of the right-of-way.

During the inspection, the presence of recent trash, recent features and existing disturbances within individual project areas was noted. Isolates were mapped relative to a known point using a Brunton compass and pacing. Locations of isolates were plotted on maps provided by Phillips Petroleum. When isolates were encountered, an area with a radius of at least 25 feet (8 meters) around the isolate was closely inspected for features and additional artifacts.

Sites located during the inspection were mapped in a similar manner.

In report preparation, UTM Coordinates were plotted from the USGS White Mesa Village, Utah, 15-Minute Quadrangle (Figure 2). Legal descriptions were made using maps enlarged from the 15-minute quadrangle (Figures 4-9). The project area is on unplatted land, therefore, some discrepancies occur between the two map scales.

PHYSIOGRAPHY AND ENVIRONMENT

The project locations are confined to an area 3.2 kilometers x 4 kilometers (2 miles x 2.5 miles) located approximately 8 kilometers (5 miles) south of Montezuma Creek, San Juan County, Utah. The area is bordered on the north by Flat Top Mesa and on the south by White Mountain Mesa. Blue Hogan Wash and Sahgzie Creek delineate the western and eastern boundaries, respectively (see Figures 1 and 2). Several zones differing in soils, vegetation, topography, terrain and elevation are represented within the survey area. The major characteristics of these zones are outlined below.

Zone A - Mesa Slopes

This zone is confined to the northern slopes of White Mesa Mountain. Terrain is broken and eroded with a slope of up to 32%. Soils are poorly developed and include locally sandy shallow soils on narrow benches and clayey soils with bentonite deposits in badland formations. Sandstone outcrops and exposed bedrock sandstone are common. Surface deposits include lag gravels and numerous sandstone spalls. Numerous arroyos dissect the slopes. Vegetation is generally sparse and includes rabbitbrush, shadscale, Russian thistle and prickly pear cactus. Ground cover ranges from 0% to 20%. Maximum elevation is approximately 1,570 meters (5,150 feet).

Zone B - Badland Formations

This zone includes erosional remnants of both sandstone capped badland hills and somewhat more extensive low mesa shaped remnants.

PROJECT AREA




Figure 1
Report R4-SIC-071R

R 23E

R 24E




Figure 2

Report 84-SJC-071B

These formations are characterized by steep slopes frequently dissected by arroyos. Soils are generally clayey, shallow and poorly developed with localized bentonitic clay deposits common. In many areas broken, platy shale is exposed. Vegetation is generally quite sparse and limited to scattered snakeweed and grasses. Ground cover ranges from 0% to 20%. In general, the badland formations characterized by Zone B are similar to Zone A except that they are generally lower in elevation, averaging 1,433 meters (4,700 feet), and contain areas with shaley outcrops.

Zone C - Stabilized and Semistabilized Dunes

This zone characterizes the majority of the project locations. Dunes are found in a variety of topographic situations including ridges, arroyo bottoms and mesa tops and slopes. In some areas they are found on or adjacent to badland formations. Terrain ranges from level to rolling and gently rolling with blownout areas common. In some instances the blowouts have acted as seasonal catchments, as evidenced by surface clay deposits left behind as water evaporates or filters down. Soils within the dunal deposits are sandy to very sandy loams and are generally reddish-brown in color. The deposits range from shallow, where the old blowouts have exposed bedrock sandstone or shale, to quite deep. Entrenched arroyos through dunal deposits were noted to exceed 3 meters in depth in some places. Vegetation is of the desertscrub community and includes blackbrush, sagebrush, shadscale, ephedra, rabbitbrush, snakeweed, echinocereus, narrowleaf yucca, prickly pear cactus and Russian thistle. A wide variety of grasses and annuals is also represented and includes grama, galleta, ricegrass,

needle & thread, ring muhly, six-weeks fescue, brome, dropseed, crested wheat, alkali sacaton, globemallow, white asters and lupine. Not all species are represented in all areas and additional unidentified shrubs and grasses are present. Ground cover varies greatly from as little as 10% to as much as 80%. In general, elevations range between 1,425 meters to 1,479 meters (4,675 feet to 4,850 feet).

Zone D - Active Dunes

This zone includes those dunal deposits which are unstable and shifting. Topographic context is the same as for Zone C and active dunes are frequently associated with stabilized dunes. These dunes are long and rounded. Blowouts are common and the white sand of the active dunes displays characteristic wave patterns. The depth of the deposits is variable as with the stabilized and semistabilized dunes. Vegetation is limited to sparse, scattered grasses and low shrubs. Elevations are the same as for Zone C.

Discussion of Zones

No project areas described in this report are located in Zone A. Moreover, only portions of two project areas (Ratherford Units 17-33 and 18-24) are located in areas characterized by Zone B. All six of the project areas contain Zone C deposits and three have Zone D deposits in conjunction with semistabilized dunes. As indicated in the preceding description of the stabilized and semistabilized dunal deposits, these areas are all remarkably similar in terms of soils and terrain. They differ primarily in terms of topographic setting.

direction of slope and degree to which they have been dissected by erosion. The areas represented by Zone C are considered most likely to contain subsurface in-situ cultural materials; 75% of the archaeological sites and the overwhelming majority of the isolates were located in stabilized and semistabilized dune situations. The possibility of subsurface cultural remains with no surface indications in the deposits is acknowledged as quite real.

No project locations were located completely within the active dunes described as Zone D. Active dunes were encountered on portions of two of the project areas described in this report. Potential for cultural materials, with or without surface indications, within these deposits is also considered to be high. Both sites and isolates were located in Zone D. The major distinction between Zones C and D in terms of cultural resources is the likelihood that materials in Zone D are likely to be encountered only in blowouts and are much more likely to be out of context.

Water Sources

Within the project area water sources are generally limited to seasonally running washes, the largest of which are Blue Hogan Wash and Sahgzie Creek. The San Juan River is located approximately 3.2 kilometers (2 miles) northeast of the most easterly portions of the project area. Only one permanent water source, a spring in the southern half of Section 18, is shown on USGS maps. The presence of tamarisk in the southern portion of Section 21 along an east trending feeder of Sahgzie Creek suggests the existence of either an underground

water source or seasonally accumulating water. An earthen dam of relatively recent construction (now broken) is located on Blue Hogan Wash in the NW 1/4 of Section 19 and provided a relatively large catchment area. Tamarisk is present below the dam although no water was present at the time of the survey. In addition, as noted earlier, some catchments seasonally hold small amounts of water. A windmill in the SW 1/4 of Section 24, T. 41 S., R. 23 E., just west of the project area, and a flowing well in the NW 1/4 of Section 12, T. 41 S., R. 23 E., just west of the project area, are also used by local inhabitants for watering livestock. A few isolated, seasonal springs or seeps are reported in the area, however, their locations are not known.

Fauna

Little wildlife was seen within the project area during the archaeological inspection. Lizards were seen frequently and one cottontail rabbit was observed. Large and small rodent burrows were noted and coyote were heard during the survey of the slopes of White Mesa Mountain. According to Mr. Isaacs, hawks are also frequently seen in the vicinity of White Mesa Mountain.

Present Day Land Use

The project area is located in the heart of the Aneth Oil Field where extensive development related to energy exploration and production over the past twenty years has occurred. Well locations dot the area and numerous roads, powerlines, above and below ground pipelines and oil field camps are a direct result of this development.

The area is also used extensively by local Navajo families. Occupied and unoccupied houses and hogans occur frequently throughout the project area. Although no interviews were conducted with customary land users, due in part to the fragility of relations between oil companies and local Navajos, it was noted that the area is intensively utilized for grazing activities. Moreover, both functional sweat houses and the remains of sweat houses attest to the use of the area in ritual activity. In the absence of interviews, it is impossible to know whether sacred areas or graves are present within the project area. Nothing resembling grave sites was noted during the inspection of individual project locations.

RECORDS SEARCH

Prior to the initiation of fieldwork, a records search was conducted using information available at the Cultural Resources Management Program, San Juan College and the Navajo Nation Cultural Resource Management Program, Farmington Office, as well as through phone contact with both the Navajo Nation Cultural Resource Management Program, Window Rock, and several local contract archaeology firms.

Numerous large and small archaeological surveys and excavations have been conducted in southeastern Utah. The majority of these projects have been located north of the San Juan River to the north, northeast and northwest of the project area. Projects have been related to both large parcel inventory surveys (see for example Fike and L'indsay, 1976) and energy and economic development (see for example

Hewett, Powers and Kemrer, 1979; Berge, 1975; Langenfeld, 1982; Reed, 1983). Sites dating from the Archaic Period through recent Historic Periods have been documented.

Within the project area itself few sites have been documented. According to a contact at Phillips Petroleum, previous archaeological surveys in the Phillips Field had been conducted by Complete Archaeological Service Associates of Cortez. Only one site has been recorded by C.A.S.A., and it is a lithic scatter with diagnostic tools dated to the San Jose Phase of the Archaic Period (L. Hammack to R.P. Watson, personal communication). The site is located in the SE 1/4 of the NE 1/4 of Section 29, T. 41 S., R. 24 E. The site number is unknown and its location was plotted on Figure 3 by use of UTM's provided by Mr. Hammack of C.A.S.A.

Two additional sites within the Phillips Field have been documented by the Navajo Nation Cultural Resource Management Program (Martin, 1983). These sites are also located in Sections 29 and 16, T. 41 S., R. 24 E. UT-C-54-3 is described as a permanent Historic Navajo, sheep camp with two corrals or lambing pens and possible hogan. UT-C-54-4 is an undated lithic scatter containing complete and broken flakes and burned sandstone. The locations of these sites were also plotted on Figure 3 on the basis of UTM's provided in the report. The actual site location in Section 16 is uncertain. On maps provided by Phillips Petroleum, a large site area is shown in the SW 1/4; however, it has not been determined if this site was recorded by Navajo Nation Cultural Resource Management Program or C.A.S.A.

According to Mr. Isaacs, the Navajo Tribal Utility Authority has worked on the Phillips Lease Area within the last year. In the absence of a known project number, however, it is not possible to obtain information concerning a cultural resource inventory related to the project (Joe Anderson, personal communication).

Three additional sites north of the project area and south of the San Juan River have been recorded by the Navajo Nation Cultural Resource Management Program. Those sites are briefly described below and were plotted on Figure 3 on the basis of information provided by the source listed:

- UT-C-54-1: Post 1970 Navajo site (Phillip Stewart, personal communication).
- UT-C-54-2: Lithic/ceramic/ground stone scatter located in blowouts; Anasazi, Basketmaker III-Pueblo I (Phillip Stewart, personal communication).
- UT-C-54-5: Lithic scatter; undated (McEnany, 1984).
- SJC-727: Rubble mound, lithics, ceramics.

None of the previously recorded sites will be impacted by the proposed land modifications.

Name: Ratherford Unit 19-11 (Figure 6)

Land Jurisdiction: Navajo Nation

Legal Description: The proposed well is in the Center of the NW 1/4 of the NW 1/4 of Section 19, T. 41 S., R. 24 E., S.L.P.M., San Juan County, Utah. The center stake is 660 feet from the north line and 660 feet from the west line. Access will run from the Center of the North 1/2 of the SW 1/4 of the NW 1/4, into the Center of the South 1/2 of the NW 1/4 of the NW 1/4 of Section 19. The flow line will run from the Center of the South 1/2 of the NW 1/4 of the NW 1/4, through the Center of the North 1/2 and the SE 1/4 of the NW 1/4, and across the South 1/2 of the SE 1/4 of the NW 1/4 of Section 19.

Elevation: 1,436 meters (4,708 feet)

UTM Coordinates: Well = Zone 12; 648,225 mE; 4,119,620 mN.
Access E-O-L/Flow Turn = Zone 12; 648,200 mE;
4,119,270 mN.
Flow E-O-L = Zone 12; 648,845 mE; 4,119,040 mN.

Actual Project Area: Well = 107 m. x 107 m. (350' x 350')
Access = 12.2 m. x 290 m. (40' x 950')
Flow = 3 m. x 701 m. (10' x 2,300')
TOTAL: 1.7 hectares (4.2 acres)

Actual Survey Area: 137 m. x 137 m. (450' x 450')
23 m. x 290 m. (75' x 950')
7.6 m. x 701 m. (25' x 2,300')
TOTAL: 3.0 hectares (7.6 acres)

Physiography and Environment:

The project area is located on a series of low dunal ridges east of Blue Hogan Wash in Zone C. Terrain slopes gently to the south. South and west of the proposed well location is a relatively level area of stabilized dunes cut by a southwest trending arroyo. The access and flow line cross the top of the dunal ridge. The flow line proceeds along an existing road and two-track across Zone D. Blowouts are present along the flow line and access routes. Shale and sandstone outcrops and boulders are present on the location. Localized areas of

naturally stained soil from decomposing shale are present on and near the well location.

Cultural Resources:

Two archaeological sites were located during the inspection. SJC-1108, a Pueblo II artifact scatter, is located adjacent to existing road south and west of the project area (Figures 6 and 12) and will not be directly impacted by any construction activities. SJC-1107 is located at the edge of the buffer zone at the south corner of the proposed well location (Figures 6 and 11). This site also dates to the Pueblo II Period and contains an undisturbed roomblock, storage area and midden. The sites may be related. In addition, four isolates were located (Figure 6). I.O.'s 6 and 7 are probably related to Sites SJC-1107 and/or SJC-1108. I.O.'s 8 and 9 are of unknown cultural affiliation. None of the isolates appear to represent surface manifestations of subsurface cultural materials. The I.O.'s are more fully described in Table 1.

Recommendations:

SJC-1108 is outside the project area and will not be directly impacted by proposed land modification activities. Its low visibility should assist in protecting it from secondary impacts such as collecting activities although it is difficult to assess the potential of such secondary impacts.

SJC-1107 is located at the edge of the buffer zone of the proposed location across an arroyo from the reserve pit. The arroyo should provide a natural barrier between construction equipment and the site

during both construction and rehabilitation activities. The site should not suffer any direct impacts as a result of construction activities. As with SJC-1108, the nature of secondary impacts is more difficult to assess. The site is relatively close to the proposed location and has the type of features susceptible to collection and pothunting activities. Short of moving the well location, there is probably no way of insuring that the site will not be impacted by secondary activities.

Therefore, it is recommended that archaeological clearance be granted for the 19-44 project area with the stipulation that no mechanical disturbance or vehicular traffic be allowed southwest of the arroyo south and west of the proposed pit area. If these stipulations are accepted and adhered to, SJC-1107 should be adequately protected from direct impacts without the necessity of an archaeological monitor during construction.

29.
R 24E

unsurveyed lands

Ratherford Unit 19-11
660' FNL / 660' FWL
Sect. 19, T 41S, R 24E
San Juan County Utah
owner: Navajo Res.

Site SJC 1109

IO# 84-SJC-071B-9

T 41S

IO# 84-SJC-071B-8

Site SJC 1108

IO# 84-SJC-071B-7

IO# 84-SJC-071B-6

Ratherford Unit 19-44
660' FSL / 660' FEL
Sect. 19, T 41S, R 24E
San Juan County, Utah
owner: Navajo Res.

Site SJC 1107

paved road

Scale: 1" = 1000'

WHITE MESA VILLAGE, UTAH
#3700-W10915/15

1962

AMS 4158 III-SERIES V797



 proposed well
 proposed flow line

Figure: 6

Report 84-SJC-071B

DISCUSSION OF CULTURAL RESOURCES

A total of five isolates were located during the inspection. Isolates were located on only two project areas - the Ratherford Units 18-24 and 19-44. Two of the isolates (I.O.'s 6 and 7) are located in spatial proximity to sites (SJC-1107 and SJC-1108). I.O. 3 may be associated with a prehistoric component of SJC-1106 (see site description). Given that all six of the project areas contained archaeological sites, the number of isolates recorded seems low. It is noted, however, that while 1.6 isolates per 10 hectares (24.7 acres) were recorded during the nonsite-bearing portion of the survey (Langenfeld and Hooton, 1984), 2.6 isolates per 10 hectares (24.7 acres) were found in the project areas under discussion here. While the relative number of isolates per hectare increases, it does not do so substantially. The suggested reason for this is that artifacts that might have otherwise been recorded as isolates were incorporated into sites during this portion of the survey. In terms of absolute numbers of isolates recorded during the survey, it is suggested that the low numbers are probably the result of the nature of surface deposits in the project area. Isolates are more likely to be obscured in dunal deposits.

The isolates recorded during this portion of the survey are fully described in Table 1.

A total of eight archaeological sites was recorded during the survey. Site density can only validly be calculated by using total survey area size. A total of approximately 55 hectares (140 acres)

TABLE 1: Summary of Isolated Occurrences

I.O. #	Well Name	Loc.	Sec.	T	R	UTM Coordinates	Description	Comments
3	18-24	Center, N 1/2, SE,SW	18	41 S	24 E	Zone 12; 648,535 E 4,120,105 N	One complete secondary quartzite flake. Single-struck platform. Distal termination hinged. No retouch present. Cultural affiliation unknown.	Information potential exhausted with recording.
6	19-44	Center, SE,SE	19	41 S	24 E	Zone 12; 649,425 E 4,118,445 N	One black-on-white sherd. Heavily tempered with medium sized quartz with small amounts of angular igneous black rock. Heavily slipped and polished interior and exterior. Black paint present exterior. Vessel shape unknown. Design style similar to Mancos Black-on-white (Pueblo II-III, A.D. 900-1150).	Probably related to Site SJC-1107 or SJC-1108. Information potential exhausted with recording.
7	19-44	Center, SE,SE	19	41 S	24 E	Zone 12; 649,450 E 4,118,470 N	One broken tertiary flake of white chert. Platform preparation and distal termination unknown. Lateral edges show some nibbling either from use wear or as a result of exposure to elements. Cultural affiliation inferred as Pueblo II-III (A.D. 900-1150) based on proximity to Sites SJC-1107 & 1106.	Information potential exhausted with recording.

TABLE 1 (Continued)

I.O. #	Well Name	1,1,1	Sec.	T	R	UTM Coordinates	Description	Comments
8	19-44	NW,NE,SE	19	41 S	24 E	Zone 12; 649,390 E 4,118,905 N	One broken gray quartzite flake. Platform prepared, distal termination unknown. No retouch present. Cultural affiliation unknown.	Information potential exhausted with recording.
9	19-44	SW,SE,NE	19	41 S	24 E	Zone 12; 649,290 E 4,119,150 N	One complete secondary quartzite flake. No platform preparation, distal termination hinged, no retouch present. Maximum length 44 m., maximum width 41 mm. Cultural affiliation unknown.	Located on road berm approximately 275 m. (900') north of I.O. #8. Information potential exhausted with recording.

were inspected during the survey. An average of 1.5 sites per 10 hectares (approximately 1 site per 20 acres) were located. This would suggest that given similar topography and terrain an average of over 30 sites per section can be anticipated.

All archaeological sites located during the inspection were found in dunal deposits. As indicated earlier, 75% of the sites are located in Zone C type dunes. The remaining 25% are located in active dunal deposits. Nineteen of the twenty total project areas contained either stable or active dunes, and over 40% of those project areas contained sites.

Prehistoric sites account for 88% (7) of all recorded sites and the one historic site (SJC-1105) may contain a prehistoric component in the form of an undated lithic scatter. Among the prehistoric sites and components, 63% are lithic scatters and 25% are artifact scatters, neither of which contains discernible surface features. Only 12% (1) of the sites shows clear evidence of having functioned as a habitation.

With the exception of SJC-1106, lithic scatters are undated. None contain clearly diagnostic chipped stone artifacts. One of the undated lithic scatters (SJC-1104) contains artifacts made of high-quality raw material which exhibit a quality of flaking and finishing frequently associated with Archaic sites. Based on a small surface sample and the known tendency for curation and reuse of Archaic chipped stone tools by later inhabitants, the suggestion that the site is Archaic in origin is tenuous at best. One Archaic site has been documented in Section 29 (see "Records Search" section). Anasazi Puebloan Period dates have been assigned to 50% (4) of the prehistoric sites and components on the

basis of ceramics. As indicated by the "Records Search" section of this report, Anasazi sites are not extremely well documented in the general vicinity of the project area. The majority of the Anasazi sites recorded during this survey appear to date between A.D. 700-1300; 75% of the Anasazi sites appear to have been classified as limited or specialized activity sites. This term is used to define all those sites that exhibit no surface indications of year-round dwellings. Limited activity sites may have been occupied once or reused periodically. Artifact types on most of the "limited activity" sites suggest that more than one activity was being carried out.

The one historic Navajo site appears to have functioned as a permanent sheep camp. Additional information concerning this site could probably be obtained by interviews with customary land users.

Table 2 presents a summary of archaeological sites by type.

In sum, the variety of sites recorded during the survey appears consistent with previously recorded sites in the vicinity, although the proportion of Puebloan sites appears somewhat higher. Moreover, the project area does not appear to have represented a highly desirable location for permanent habitation sites. This may be explained, in part, by the general paucity of natural resources (i.e. wood, permanent water, sheltered locations) within the area. All these resources are abundantly available closer to the San Juan River. The project area more likely represents a locus for a variety of specialized activity sites.

TABLE 2: Summary of Archaeological Sites

Site Number	Morphological Type	Functional Type	Cultural Affiliation
SJC-1104	Lithic scatter	Unknown	Unknown
SJC-1105	Lithic scatter; foundation, trash	Unknown; sheep camp	Unknown Navajo
SJC-1106	Lithic scatter	Unknown	Anasazi; BM II-P I
SJC-1107	Rubble mound, midden, artifact scatter	Habitation	Anasazi, P II
SJC-1108	Artifact scatter	Limited Activity	Anasazi, P II
SJC-1109	Lithic scatter	Unknown	Unknown
SJC-1110	Artifact scatter	Limited Activity	P II-P III
SJC-1111	Lithic scatter	Lithic Reduction	Unknown

SUMMARY OF RECOMMENDATIONS

Table 3 presents a summary of the recommendations chosen from those options outlined in the "Project Locations" section of the report. With the exception of Sites SJC-1109 and SJC-1111, all the prehistoric sites are suggested to have additional research potential and should be avoided. Although the research potential of Site SJC-1109 and SJC-1111 appears severely limited due to their deflated condition, each is acknowledged as a possible indicator of additional subsurface cultural deposits in the vicinity.

In the event that any or all of the recommendations in this report are accepted it is suggested that a compliance check be conducted following the initiation of construction activities to insure that stipulations are being followed.

In the event that any previously undiscovered archaeological materials are encountered during the course of construction activities, work in the immediate area should cease immediately and the B.I.A. Area Archaeologist should be notified.

Final clearance is the prerogative of the B.I.A. Area Archaeologist and will be granted upon review of this report at his discretion.

TABLE 3: Summary of Recommendations

Site Number	Location	Recommendation
SJC-1104	17-33 Flow Line	Restrict vehicular activity to existing, bladed road southwest of proposed flow line.
SJC-1105	18-24 Access	Monitor of access construction at western end of originally proposed route. Collect surface artifacts.
SJC-1106	18-33 Well Location	Decrease east/west pad dimensions from 350' to 325'. Restrict mechanical disturbance to an area 175' west of center stake.
SJC-1107	19-11 Well Location	Restrict mechanical disturbance and vehicular traffic to area north and east of arroyo on pit side of pad.
SJC-1108	19-11 Flow Line	Outside project area. No recommendation required.
SJC-1109	19-44 Well Location	Monitor well pad construction.
SJC-1110	21-22 Well Location	Move center stake 125' south and rotate pad layout 90 degrees to the east.
SJC-1111	21-22 Access	No avoidance or mitigation is recommended.

BIBLIOGRAPHY

- Fike, Richard E. and LaMar W. Lindsay
1976 Archaeological Survey of the Bluff Bench/San Juan River and White Mesa Areas, San Juan County, Utah, 1973-1974. In Antiquities Section Selected Papers Volume III, Numbers 9-11, Pgs. 1-23. Salt Lake City: Utah State Historical Society, Department of Development Services, Division of State History.
- Hewett, Nancy S., Margaret A. Powers and Meade F. Kemrer
1979 An Archaeological Survey and Evaluation of Resources Along the San Juan River Near Aneth, Utah. Division of Conservation Archaeology, Contributions to Anthropology Series 46.
- Langenfeld, Kristin
1982 Archaeological Surveys of 24 Proposed Drill Pad Conversions Near Montezuma Creek, San Juan County, Utah (CRMP-82-077). On file, Navajo Nation Cultural Resource Management Program, Window Rock, Arizona.
- Langenfeld, Kristin and L. Jean Hooton
1984 Archaeological Surveys of 13 Proposed Well Locations and Associated Flow Lines and Access Routes in San Juan County, Utah, Conducted for Phillips Petroleum (84-SJC-071A). On file, Cultural Resources Management Program, San Juan College, Farmington, New Mexico.
- Lipe, William
1970 Anasazi Communities of the Red Rock Plateau, Southeastern Utah. In Reconstructing Prehistoric Pueblo Societies, edited by William A. Longacre, Pgs. 84-139. Albuquerque: University of New Mexico Press.
- Martin, Rena
1983 An Archaeological Survey of Surface Flowlines and Assorted Parcels of Land in San Juan County, Utah (CRMP-83-336). On file, Navajo Nation Cultural Resource Management Program, Farmington, New Mexico.
- McEnany, Tim
1984 An Archaeological Survey of Two Well Locations Near Montezuma Creek, Utah for the Chuska Energy Company (CRMP-84-36). On file, Navajo Nation Cultural Resource Management Program, Farmington, New Mexico.
- Reed, Alan C.
1983 An Archaeological Survey of A Segment of Seismic Line R-3-83 in San Juan County, Utah. Contributions to Anthropology Series No. 749. On file, Division of Conservation Archaeology, Farmington, New Mexico.

LAF

Field No. 19-11 Well Location

LABORATORY OF ANTHROPOLOGY, MUSEUM OF NEW MEXICO
 ARCHEOLOGICAL SITE SURVEY FORM

LA No. _____ Site Name _____ Other Inst. # SJC-1107
 MNM Proj. # _____ UTM: Zone 12 E 649420 N 4118360

Legal Desc. T41 S24 E24 EXM Sec. 19

SW 1/4 of the SE 1/4 of the SE 1/4

Unplatted _____ Grant _____ Owner & Address Navajo Nation

*Map Reference: White Mesa Village, Utah Date: 1962 Scale: 1:62500

County San Juan State Utah Nearest Named Drainage Blue Hogan Wash

Locational Desc.: Recognized Landmarks White Mesa Mountain

Site Type: rubble mound, midden, storage area, artifact scatter

Site Size: Length 34 m. n/s width 45 m. e/w Elevation (# of Feet) 4,800

Topographic Setting (Location & Access): the site is located approximately
60 m. east of an existing, bladed road.

<input type="checkbox"/> arroyo/wash	<input type="checkbox"/> flood plain/	<input type="checkbox"/> plain/flat
<input type="checkbox"/> base of cliff	<input type="checkbox"/> valley bottom	<input type="checkbox"/> playa
<input type="checkbox"/> bench	<input type="checkbox"/> hill top	<input type="checkbox"/> ridge
<input type="checkbox"/> blowout	<input type="checkbox"/> hill slope	<input type="checkbox"/> saddle
<input type="checkbox"/> canyon rim	<input type="checkbox"/> low rise	<input type="checkbox"/> base talus slope
<input type="checkbox"/> cave	<input type="checkbox"/> mesa	<input type="checkbox"/> terrace
<input type="checkbox"/> cliff/scarp	<input type="checkbox"/> mountain	<input type="checkbox"/> other (specify) <u>base and</u>
<input type="checkbox"/> constricted cyn	<input type="checkbox"/> mt. front/foothill	<input type="checkbox"/> <u>top of low ridge</u>
<input type="checkbox"/> dune	<input type="checkbox"/> open canyon floor	

Local Vegetation rabbitbrush, snakeweed, prickly pear cactus, yucca, ricegrass

Ecological Zone: forest _____ woodland _____ scrubland _____ grassland _____

desertscrub, X marshland _____ other (specify) _____

*Form must be accompanied by photocopy portion of USGS map showing T.,
 R., scale and quad name.

Soil Type: rocky___ gravelly___ sandy X clayey___ other _____

Local Outcrops: sandstone X shale___ limestone___ basalt___ tuff___
other (specify) _____

Nature & estimated depth of cultural deposits: probably less than 1 m.

Arch. Status: Amount and Type of Work Past and Present No known past work. Present work limited to site mapping and recording.

BLM Category I Rec'd N/A

BLM Category II Rec'd N/A

National and/or State Register Status:

- ☐ On State Register
- ☐ On National and State Register
- ☐ Recommended for National by State, on State Register
- ☐ Recommended for National and State Register
- ☐ In District, National and State
- ☐ In District, National
- ☐ In District, State
- ☐ Recommended and rejected
- ☐ Insufficiently evaluated, potential unknown
- ☒ Not nominated, potentially significant (archaeologist's rec'd)
- ☐ Not nominated, does not appear to be significant (arch. rec'd)

Condition of Site: intact___ grazed X eroded X mech. disturbance___
vandalized___ other _____

Mitigation: avoid X monitor___ test___ excavate___ not required___

Surveyed for Phillips Petroleum

Record Form: Surv. Forms X Excav. Forms___ Sketch Map X Photos X

Loc. of Forms, Maps, Photos San Juan College, Cultural Resources Management Program

Surface and/or Subsurface Collections: yes___ no X Strategy _____

Location of Collected Artifacts N/A

Previous Collections? ? When _____ Repository _____

Is there another site close by? Yes LA or Field Identif.# SJC-1108

Artifact Density: ~~XX~~ 10's. ~~XXXXXXXXXXXXXX~~ 2-3/m² in concentrations per unit.

Time/Diagnostic Artifacts: Black-on-white pottery, Corrugated pottery

Field No. _____

Other Inst. # SJC-1107No. of Temporal Components 1

(Earliest to Latest)

Temporal Component (1)

Features rubble mound, storage area, midden, artifact scatterCulture Anasazi Period P II Phase _____Site Function: habitation Best Date A.D. 900-1150Method of Date: ceramics

Temporal Component (2)

Features _____

Culture _____ Period _____ Phase _____

Site Function _____ Best Date _____

Method of Date _____

Temporal Component (3)

Features _____

Culture _____ Period _____

Phase _____

Site Function _____ Best Date _____

Method of Date _____

Additional Temporal Components

Langhorne

Langhorne

Fiel. No. _____

Other Inst. # SJC-1107

published Reference:

date June, 1984Institution San Juan College, Cultural Resources Management Program, Farmington, NMAuthor and Title Kristin Langenfeld, Archaeological Surveys of Six Proposed Well Locations and Associated Flow Lines and Access Routes in San Juan County, Utah, Conducted for Phillips Petroleum Company (#84-SJC-071B)

Remarks: The site consists of a rubble mound, associated midden, artifact scatter and storage area. The rubble mound measures approximately 4.5 m. n/s x 5.5 m. e/w and consists of unshaped and shaped sandstone blocks. One alignment of three blocks was noted in the northeast corner of the mound. The size of the rubble mound appears to indicate the presence of two, possibly three, rooms. Approximately 7 m. south of the rubble mound is the remains of a collapsed storage area under the north face of a large free-standing sandstone boulder. The storage area was constructed of medium sized pieces of tabular sandstone. Rubble covers an area approximately 4 m. in length and approximately 1.5 m. in depth under the overhang of the boulder. Original height of the room is indeterminate. A midden area measuring approximately 7 m. in diameter and containing chipped and ground stone and ceramics is located approximately 8 m. southwest of the rubble mound. This area also contains ash, charcoal and stained earth. Artifacts are generally concentrated in and around the midden and rubble mound. The scatter becomes lighter toward the east and west site boundaries on the top of the low rise. No artifacts were located on the north ridge slope toward a slightly entrenched arroyo or south of the two free-standing sandstone boulders. Chipped stone artifacts include cores, primary, secondary and tertiary flakes and bifaces. Ground stone includes at least two mano fragments. Pottery types on the site include a high proportion of corrugated gray wares and lesser numbers of black-on-white wares. Field analysis of sherds indicated quartz as the major tempering material in gray wares. At least one black-on-white sherd was tempered with about equal amounts of quartz and angular black volcanic rock. The design type is similar to Cortez Black-on-white. The site appears to have functioned as a habitation site with a relatively full range of activities represented including all stages of tool manufacture and maintenance, food processing and preparation and storage. The presence of corrugated utility wares and painted ceramics suggests a Pueblo II occupation. The site shows no evidence of having been vandalized although aluminum cans close by may be associated with casual surface collecting activities.

Field Recorder K. Langenfeld/L.J. HootonDate 5/22/84Lab Recorder Kristin LangenfeldDate 5/29/84

Site SJC 1107
SW $\frac{1}{4}$, SE $\frac{1}{4}$, SE $\frac{1}{4}$
Section 19
T 41S, R 24E
San Juan Co., Utah
Mapped: 22 May 1984




Figure 11

LA#

Field No. 19-11 Flow Line

LABORATORY OF ANTHROPOLOGY, MUSEUM OF NEW MEXICO
 ARCHEOLOGICAL SITE SURVEY FORM

LA No. _____ Site Name _____ Other Inst. # SJC-1108
 NMN Proj. # _____ UTM: Zone 12 E 649615 N 4118495

Legal Desc. T 41 N/S R 24 E/W Sec. 19

NW 1/4 of the SE 1/4 of the SE 1/4

Unplatted _____ Grant _____ Owner & Address Navajo Nation

*Map Reference: White Mesa Village, Utah Date: 1962 Scale: 1:62500

County San Juan State Utah Nearest Named Drainage Blue Hogan Wash

Locational Desc.: Recognized Landmarks White Mesa Mountain

Site Type: Artifact scatter

Site Size: Length 41 m. n/s Width 46 m. e/w Elevation (# of Feet) 4,800

Topographic Setting (Location & Access): the site is located in and adjacent to an existing, bladed road.

<input type="checkbox"/> arroyo/wash	<input type="checkbox"/> flood plain/	<input type="checkbox"/> plain/flat
<input type="checkbox"/> base of cliff	<input type="checkbox"/> valley bottom	<input type="checkbox"/> playa
<input type="checkbox"/> bench	<input type="checkbox"/> hill top	<input checked="" type="checkbox"/> ridge
<input type="checkbox"/> blowout	<input type="checkbox"/> hill slope	<input type="checkbox"/> saddle
<input type="checkbox"/> canyon rim	<input type="checkbox"/> low rise	<input type="checkbox"/> base talus slope
<input type="checkbox"/> cave	<input type="checkbox"/> mesa	<input type="checkbox"/> terrace
<input type="checkbox"/> cliff/scarp	<input type="checkbox"/> mountain	other (specify) _____
<input type="checkbox"/> constricted cyn	<input type="checkbox"/> mt. front/foothill	_____
<input type="checkbox"/> dune	<input type="checkbox"/> open canyon floor	_____

Local Vegetation rabbitbrush, snakeweed, ricegrass, prickly pear cactus, grasses.

Cells: _____

Illection: _____

Ecological Zone: forest _____ woodland _____ scrubland _____ grassland _____

desertscrub ☒ marshland _____ other (specify) _____

*Form must be accompanied by photocopy portion of USGS map showing T., R., scale and quad name.

Soil Type: rocky___ gravelly___ sandy X clayey___ other___

Local Outcrops: sandstone___ shale___ limestone___ basalt___ tuff___
other (specify)___

Nature & estimated depth of cultural deposits: probably less than 1 m.

Arch. Status: Amount and Type of Work Past and Present no known past work. Present work limited to site recording and mapping.

BLM Category I Rec'd N/A

BLM Category II Rec'd N/A

National and/or State Register Status:

- ☐ On State Register
- ☐ On National and State Register
- ☐ Recommended for National by State, on State Register
- ☐ Recommended for National and State Register
- ☐ In District, National and State
- ☐ In District, National
- ☐ In District, State
- ☐ Recommended and rejected
- ☐ Insufficiently evaluated, potential unknown
- ☒ Not nominated, potentially significant (archaeologist's rec'd)
- ☐ Not nominated, does not appear to be significant (arch. rec'd)

Condition of Site: intact___ grazed___ eroded X mech. disturbance X
vandalized___ other___

Mitigation: avoid___ monitor___ test___ excavate___ not required X (outside project area)

Surveyed for Phillips Petroleum

Record Form: Surv. Forms X Excav. Forms___ Sketch Map X Photos X

Loc. of Forms, Maps, Photos San Juan College, Cultural Resources Management Program

Surface and/or Subsurface Collections: yes___ no X Strategy___

Location of Collected Artifacts N/A

Previous Collections? ? When___ Repository___

Is there another site close by? Yes LA or Field Identif.# SJC-1107

Artifact Density: ~~10's~~ 10's, ~~XXXXXX~~ average $1/m^2$
per unit.

Time/Diagnostic Artifacts: Corrugated utility wares, black-on-white wares

No. of Temporal Components 1

(Earliest to Latest)

Temporal Component (1)

Features artifact scatterCulture Anasazi Period Pueblo II Phase _____Site Function: ? limited activity Best Date A.D. 900-1150Method of Date: ceramics

Temporal Component (2)

Features _____

Culture _____ Period _____ Phase _____

Site Function _____ Best Date _____

Method of Date _____

Temporal Component (3)

Features _____

Culture _____ Period _____

Phase _____

Site Function _____ Best Date _____

Method of Date _____

Additional Temporal Components

Field No.

Other Inst. # SJC-1108

Published Reference:

Date June, 1984Institution San Juan College, Cultural Resources Management Program, Farmington, NMAuthor and Title Kristin Langenfeld, Archaeological Surveys of Six Proposed Well Locations and Associated Flow Lines and Access Routes in San Juan County, Utah, Conducted for Phillips Petroleum Company (#84-SJC-071B)

Remarks: The site consists of an artifact scatter located on the crest and south slope of a stabilized dunal ridge. Artifacts are generally confined to the south and western portions of the site and are most numerous along an old road cut that crosses the southern portion of the site in an easterly direction and in and adjacent to a slightly entrenched arroyo. Artifacts on the ridge crest are limited to a couple of large unmodified chert flakes and several plain white ware sherds. No features are present on the surface but the possibility for subsurface deposits, particularly on the southern portion of the site, is good. Some artifacts are eroding out of the cut walls of the south trending wash. Artifact types are generally similar to those noted for Site SJC-1107 and include chipped stone debris and debitage, corrugated gray wares, plain white wares and black-on-white sherds. Overall, the number of surface artifacts is less than on Site SJC-1107 located approximately 150 m. southeast. Sherds are more common than chipped stone and although no systematic recording was performed on the site tertiary flakes appear to comprise the majority of the chipped stone assemblage. Only a couple of retouched flakes were noted. Overall, a lesser number of activities are represented by the artifact assemblage on Site SJC-1107 than SJC-1108. Site SJC-1108 appears to date to the Pueblo II Period and may be a limited activity site related to the habitation site SJC-1107.

Field Recorder Kristin LangenfeldDate 5/23/84Lab Recorder Kristin LangenfeldDate 5/29/84

Site SJC 1108NW $\frac{1}{4}$, SE $\frac{1}{4}$, SE $\frac{1}{4}$

Section 19

T 41S, R 24E

San Juan Co., Utah

Mapped: 23 May 1984




Figure 12

December 2, 1965

Ratherford Unit, San Juan County, Utah -
Application No. 32773 - Request for Extension
of Time to Make Proof of Appropriation

Mr. R. M. Williams (2)
Legal Department

Phillips' Application No. 32773 to the State of Utah for appropriation of water to be used in the Ratherford Unit project was approved on September 5, 1961. One condition of the approval was that a proof of appropriation be submitted by February 28, 1963. Subsequently an extension was granted and the proof of appropriation is now due on February 28, 1966. It is not possible to determine at this time the quantity of water that will ultimately be required and this is to request your assistance in obtaining an additional extension of time before it is necessary to file the proof.

Attached is a copy of Mr. C. M. Boles' letter dated November 23, 1965, which transmits a copy of an unexecuted application for an extension of time for filing the proof from February 28, 1966, to February 28, 1971. Please examine the application as to form and, if it is acceptable, forward it to Mr. J. E. Chrisman, who will arrange for its execution. If it is your opinion that the legal firm of Senior and Senior should file the application, as was done previously, please so advise and the executed application will be returned to you.

Shofner Smith

JEC:gm
Attach.

cc: Messrs. C. W. Corbett
Attn. T. L. Osborne
C. M. Boles

12/8/65
HSC

1/10

1/10

Copied for
C. M. Bole
4-18-62 EFL:m

THE STATE OF UTAH
OFFICE OF THE STATE ENGINEER
SALT LAKE CITY

March 26, 1962



Phillips Petroleum Company
Bartlesville,
Oklahoma

Gentlemen:

RE: APPROVED APPLICATION NO. a-4025

Enclosed find Application No. a-4025 which has been approved by me. This approved Application is your authority to proceed with actual construction work which, under Sections 73-3-10 and 73-3-12, Utah Code Annotated 1953, as amended, must be diligently prosecuted to completion. The water shall be put to beneficial use and proof of appropriation filed with the State Engineer, as provided in the original application as amended by this approved change Application.

Failure on your part to comply with the requirements of the statutes may result in forfeiture of your Application.

Yours truly,

Wayne D. Criddle

Wayne D. Criddle

ADDRESS ALL COMMUNICATIONS TO:

STATE ENGINEER
403 STATE CAPITOL
SALT LAKE CITY, UTAH

js

Encl: Copy of approved application

CHANGE APPLICATION APPROVED

(Form for pending original Application)

OPERATOR Phillips Oil Co. DATE 10-5-84
WELL NAME Rathford Unit #19-11
SEC NW NW 19 T 41S R 24E COUNTY San Juan

43-037-31080
API NUMBER

Indian
TYPE OF LEASE

POSTING CHECK OFF:

☐

INDEX

☐

HL

☐☐

NID

☐

PI

☐☐

MAP

☐☐

PROCESSING COMMENTS:

Unit Well - OK on PSD (BEM - Steve Mason New Mexico)
Water of

APPROVAL LETTER:

SPACING:

☒

A-3

Rathford
UNIT

☐

c-3-a

CAUSE NO. & DATE

☐

c-3-b

☐

c-3-c

SPECIAL LANGUAGE:

☒ RECONCILE WELL NAME AND LOCATION ON APD AGAINST SAME DATA ON PLAT MAP.

☒ AUTHENTICATE LEASE AND OPERATOR INFORMATION

☒ VERIFY ADEQUATE AND PROPER BONDING

☒ AUTHENTICATE IF SITE IS IN A NAMED FIELD, ETC.

☐ APPLY SPACING CONSIDERATION

☐ ORDER _____

☒ UNIT _____

☐ c-3-b

☐ c-3-c

☒ CHECK DISTANCE TO NEAREST WELL.

☐ CHECK OUTSTANDING OR OVERDUE REPORTS FOR OPERATOR'S OTHER WELLS.

☒ IF POTASH DESIGNATED AREA, SPECIAL LANGUAGE ON APPROVAL LETTER

☒ IF IN OIL SHALE DESIGNATED AREA, SPECIAL APPROVAL LANGUAGE.



STATE OF UTAH
NATURAL RESOURCES
Oil, Gas & Mining

Scott M. Matheson, Governor
Temple A. Reynolds, Executive Director
Dianne R. Nielson, Ph.D., Division Director

4241 State Office Building • Salt Lake City, UT 84114 • 801-533-5771

October 10, 1984

Phillips Oil Company
P. O. Box 2920
Casper, Wyoming 82602

Gentlemen:

Re: Well No. Ratherford Unit #19-11 - NW NW 19, T. 41S, R. 24E
660' FNL, 660' FWL - San Juan County, Utah

Approval to drill the above referenced oil well is hereby granted in accordance with Section 40-6-18, Utah Code Annotated, as amended 1983; and predicated on Rule A-3, General Rules and Regulations and Rules of Practice and Procedure.

In addition, the following actions are necessary to fully comply with this approval:


1. Spudding notification to the Division within 24 hours after drilling operations commence.
2. Submittal to the Division of completed Form OGC-8-X, Report of Water Encountered During Drilling.
3. Prompt notification to the Division should you determine that it is necessary to plug and abandon this well. Notify John R. Baza, Petroleum Engineer, (Office) (801) 533-5771, (Home) 298-7695 or R. J. Firth, Associate Director, (Home) 571-6068.
4. Compliance with the requirements and regulations of Rule C-27, Associated Gas Flaring, General Rules and Regulations, Oil and Gas Conservation.

Page 2
Phillips Oil Company
Well No. Ratherford Unit #19-11
October 10, 1984

5. This approval shall expire one (1) year after date of issuance unless substantial and continuous operation is underway or an application for an extension is made prior to the approval expiration date.

The API number assigned to this well is 43-037-31080.

Sincerely,

A handwritten signature in dark ink, appearing to read 'R. J. Firth', with a stylized flourish at the end.

R. J. Firth
Associate Director, Oil & Gas

as
Enclosures
cc: Branch of Fluid Minerals
Bureau of Indian Affairs

DIVISION OF OIL, GAS AND MINING

SPODDING INFORMATION

API #43-037-31080

NAME OF COMPANY: PHILLIPS OIL COMPANYWELL NAME: RATHERFORD #19-11SECTION NW NW 19 TOWNSHIP 41S RANGE 24E COUNTY San JuanDRILLING CONTRACTOR Energy SerchRIG # 1SPUDDED: DATE 11-22-84TIME 6:00 PMHow Rotary

DRILLING WILL COMMENCE _____

REPORTED BY HenryTELEPHONE # 615-3480DATE 11-23-84 SIGNED GL

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE

Budget Bureau No. 1004-0137
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> Other _____		5. LEASE DESIGNATION AND SERIAL NO. 14-20-603-353	
2. TYPE OF COMPLETION: NEW WELL <input checked="" type="checkbox"/> WORK OVER <input type="checkbox"/> DEEPEN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF. REVEN. <input type="checkbox"/> Other _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME Navajo	
3. NAME OF OPERATOR Phillips Oil Company		7. UNIT AGREEMENT NAME SW-I-4192	
4. ADDRESS OF OPERATOR P. O. Box 2920, Casper, Wyoming 82602		8. FARM OR LEASE NAME Ratherford Unit	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)* At surface 660' FNL & 660' FWL, NW NW At top prod. interval reported below At total depth API #43-037-31080		9. WELL NO. #19-11	
14. PERMIT NO. --		10. FIELD AND POOL OR WILDCAT Greater Aneth	
DATE ISSUED 10-10-84		11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA Sec. 19-T41S-R24E	
15. DATE SPUDDED 11/28/84		12. COUNTY OR PARISH San Juan	
16. DATE T.D. REACHED 12/5/84		13. STATE Utah	
17. DATE COMPL. (Ready to prod.) 1/15/85		18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* GR 4708', RKB 4721.5'	
19. ELEV. CASINGHEAD --		20. TOTAL DEPTH, MD & TVD 5525'	
21. PLUG, BACK T.D., MD & TVD 5490'		22. IF MULTIPLE COMPL., HOW MANY* --	
23. INTERVALS DRILLED BY --		24. ROTARY TOOLS 0 - 5525'	
25. CABLE TOOLS --		26. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* 5427' - 5478' Desert Creek Zone I	
27. WAS DIRECTIONAL SURVEY MADE No		28. TYPE ELECTRIC AND OTHER LOGS RUN EDC/CNL, PLL/MSP	
29. WAS WELL CORDED Yes		30. CASING RECORD (Report all strings set in well)	
31. CASING SIZE		32. WEIGHT, LB./FT.	
33. DEPTH SET (MD)		34. HOLE SIZE	
35. CEMENTING RECORD		36. AMOUNT PULLED	
13-3/8"		54.5#	
9-5/8"		36#	
7"		23# & 26#	
121'		18"	
1610'		12-1/4"	
5525'		8-3/4"	
177 cu. ft. Class B		968 cu. ft. Class B, tailed in w/354 cu. ft.	
1144 cu. ft. Class B, tailed in w/300 cu. ft.			
37. LINER RECORD		38. TUBING RECORD	
39. SIZE		40. TOP (MD)	
41. BOTTOM (MD)		42. BACKS CEMENT*	
43. SCREEN (MD)		44. SIZE	
45. DEPTH SET (MD)		46. PACKER SET (MD)	
--		2-7/8"	
5327'		--	
31. PERFORATION RECORD (Interval, size and number) 5474-78', 2 SPF, 4" HSC Gun, 8 shots 5445-55', 2 SPF, 4" HSC Gun, 20 shots 5435-45', 2 SPF, 4" HSC Gun, 20 shots 5427-35', 2 SPF, 4" HSC Gun, 16 shots		32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC. DEPTH INTERVAL (MD) 5474-78' - Spot 1000 HC-2, 4 gal HAI-60. Displd w/640 gal lse wtr. (CONTINUED ON BACK)	
33. PRODUCTION		34. DATE FIRST PRODUCTION 1/15/85	
35. PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) Flowing		36. WELL STATUS (Producing or shut-in) Producing	
37. DATE OF TEST 1/24/85		38. HOURS TESTED 24	
39. CHOKER SIZE 16/64"		40. PROD'N. FOR TEST PERIOD --	
41. OIL—BDL. 80		42. GAS—MCF. 32	
43. WATER—BDL. 29		44. GAS-OIL RATIO 400	
45. FLOW. TUBING PRESS. 180#		46. CASING PRESSURE --	
47. CALCULATED 24-HOUR RATE --		48. OIL—BDL. 80	
49. GAS—MCF. 32		50. WATER—BDL. 29	
51. OIL GRAVITY-API (CORR.) 40.0		52. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) Sold	
53. TEST WITNESSED BY		54. LIST OF ATTACHMENTS None	
55. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records		56. SIGNED A. E. Stuart	
57. TITLE Area Manager		58. DATE January 25, 1985	
59. DIST ON BACK		60. *(See Instructions and Spaces for Additional Data on Reverse Side)	

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries);

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	MEAS. DEPTH	TOP TRUE VERT. DEPTH
NO. 32 CONTINUED						
Depth Interval	Amount & Kind of Material Used					
5427-55'	Spot 1650 gal 18% FE Acid w/2-1/2 gal/1000 HC-2, 4 gal/1000 Lo-Surf 259 & 2 gal/1000 HAI-60. Pump 300 gal acid then dropped 84 ball sealers evenly spaced thru 2850 gal acid, balled off twice. Displd w/1592 gal lse wtr.			LOG TOPS		
				Shinarump	2205'	
				DeChelly	2542'	
				Hermosa	4429'	
				Desert Creek		
				Zone I	5422'	
NO DST's RUN						
CORE #1 5440	5500		Cut and recovered 60'.			
CORE #2 5500	5525		Cut 25', recovered 23'.			
Distribution:						
4 - BLM, Farmington, NM						
2 - Utah O&G CC, Salt Lake City, UT						
1 - The Navajo Nation, Window Rock, AZ						
1 - B. A. Conner, H'Ville						
1 - L. R. Williamson, Denver						
1 - R. M. Coffelt (r) Pat Bertuzzi, Denver						
1 - D. L. Fraser, Denver						
1 - O. G. Poling, Denver						
1 - W.I. Owners						
1 - P. J. Adamson						
1 - File RC						

38. GEOLOGIC MARKERS

IV. WORKOVERS

None

Wells Currently Being Drilled

- #17-24 - RURT 11/6/84. Spudded 12-1/4" surf hole at 1:30 a.m. 11/7/84, Drld to 1612'. Set 9-5/8" csg at 1612', cmt'd w/700 sx Class B. Full returns, no cmt. Cmt'd 1" down backside w/100 sx Class B. Drld 8-3/4" hole to TD 5623', 11/18/84. Set 7" csg at 5594', cmt'd w/700 sx Class B. Released rig at 12:00 midnight, 11/21/84. As of November 30, 1984 - Waiting on completion unit.
- #18-44 - MI Completion Unit 11/22/84. Drld out to PBTD 5617'. Perforated 5591-5608', 34 shots, 5587-5590.5', 7 shots and 5577-5587', 20 shots. All 2 SPF, 4" hollow steel carrier gun. Spotted 500 gal 28% FE Acid. Acidized w/2875 gal acid. Flowing on test from lower Desert Creek Zone I perms 5577-5608', with a test of 138 BOPD, 55 MCFGPD, 0 BWPD. Prep to perf upper interval.
- #19-11 - Drld cond hole to 122'. Set & cmt'd 13-3/8" csg at 121' w/150 sx Class B. RURT 11/22/84. Spudded 12-1/4" surf hole at 6:00 p.m., 11/22/84. Set 9-5/8" csg at 1610', cmt'd w/700 sx Class B. Drld 8-3/4" hole to 4707'. As of November 30, 1984 - Drlg at 4707'.
- #19-31 - Shut-in, waiting to perforate upper interval.
- #19-33 - Drld to TD 5590', 11/2/84. Set 7" csg at 5590', cmt'd w/700 sx Class B. Released rig at 12:00, 11/6/84. MI completion unit 11/16/84. Drld out to PBTD 5564'. Press test csg to 1500 psi, OK. LD tbg, DC, scraper & bit. ND BOP's. NU wellhead. Released rig 11/19/84. As of 11/30/84 - Waiting on cased hole logging unit.
- #19-44 - Drld cond hole to 125'. Set & cmt'd 13-3/8" csg at 123' w/150 sx Class B. As of 11/30/84 - Waiting on rotary tools.
- #20-11 - Drld to 5573'. Core #1 5567-5627', cut & rec 60'. Core #2 5627-5657', cut & rec 30'. TD 5657', 11/5/84. Set 7" csg at 5657', cmt'd w/700 sx Class B. Released rig 11/6/84. As of 11/30/84 - Waiting on completion unit.

BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)

1. <input type="checkbox"/> OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER Satellite Gathering Station 19		3. LEASE DESIGNATION AND SERIAL NO. 14-20-603-353	
2. NAME OF OPERATOR Phillips Oil Company		4. IF INDIAN, ALLOTTEE OR TRIBE NAME Navajo	
5. ADDRESS OF OPERATOR P.O. Box 2920, Casper, WY 82602		7. UNIT AGREEMENT NAME SW-I-4192	
6. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface Center of section 19, T41S, R24E, SLPM, San Juan County, Utah		8. FARM OR LEASE NAME Ratherford Unit	
14. PERMIT NO. N.A.		9. WELL NO.	
15. ELEVATIONS (Show whether BP, RT, OR, etc.) 4760' MSL		10. FIELD AND POOL, OR WILDCAT Greater Aneth	
		11. SEC., T., R., N., OR S.E. AND SURVEY OR AREA Sec. 19 -T41S-R24E	
		12. COUNTY OR PARISH San Juan	13. STATE Utah

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON* ☐CHANGE PLANE ☐

X

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT* ☐

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Phillips Oil Company proposes to expand surface facilities to a plot 80'x 200', 0.37 acres, in the center of Section 19-T41S-R24E immediately adjacent to and inclusive of the existing 48' x 49' Section 19 gathering installation. This area is to be used to install oil well production test facilities. The area will be fenced, bermed, and reseeded upon abandonment.

5-BLM, Farmington, N.M.

2-Utah O&G CC, Salt Lake City, Utah

1-P. J. Adamson

1-B. Conner, 318-B-TRW

1-J. R. Weichbrodt

1-C. M. Anderson

1-P. Rooney

1-File

Federal approval of this action is required before commencing operations

ACCEPTED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

DATE

BY

2/7/85
John R. Bue

18. I hereby certify that the foregoing is true and correct

SIGNED

A. E. Stuart

TITLE

Area Manager

DATE

January 30, 1985

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side

Mobil Oil Corporation

P.O. BOX 5444
DENVER, COLORADO 80217-5444

May 14, 1986

Utah Board of Oil, Gas and Mining
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203

RECEIVED
MAY 16 1986

DIVISION OF
OIL, GAS & MINING

Attn: R. J. Firth
Associate Director

SUPERIOR OIL COMPANY MERGER

Dear Mr. Firth:

On September 20, 1984, The Superior Oil Company (Superior) became a wholly owned subsidiary of Mobil Corporation. Since January 1, 1985, Mobil Oil Corporation (MOC), another wholly owned subsidiary of Mobil Corporation, has acted as agent for Superior and has operated the Superior-owned properties.

On April 24, 1986, Superior was merged with Mobil Exploration and Producing North America Inc. (MEPNA), which is also a wholly owned subsidiary of Mobil Corporation. MEPNA is the surviving company of the merger.

This letter is to advise you that all properties held in the name of Superior will now be held in the name of MEPNA; and that these properties will continue to be operated by MOC as agent for MEPNA.

Attached is a listing of all wells and a separate listing of injection-disposal wells, Designation of Agent and an organization chart illustrating the relationships of the various companies. If you have any questions or require additional documentation of this merger, please feel free to contact me at the above address or (303) 298-2577.

Very truly yours,



CNE/rd
CNE8661

R. D. Baker
Environmental Regulatory Manager

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED
AUG 09 1990

FORM APPROVED
Budget Bureau No. 1004-1135
Expires September 30, 1990

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

14-20-603-353

6. If Indian: Allottee or Tribe Name

Navajo Tribal

7. If Unit or CA, Agreement Designation

Ratherford Unit
SW-I-4192

8. Well Name and No.

Ratherford Unit #19-11

9. API Well No.

43-037-31080

10. Field and Pool, or Exploratory Area

Greater Aneth

11. County or Parish, State

San Juan, Utah

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Phillips Petroleum Company

3. Address and Telephone No.

P. O. Box 1150, Cortez, CO (303) 565-3426

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

660' FNL & 660' FWL, NW NW, Sec. 19-T41S-R24E

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☐ Other
☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection

Clean out & Acidize

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

July 16, 1990 Through July 20, 1990

MI & RU well service unit 7/16/90. Pulled rods and pump. ND WH, NU BOP, COOH w/ 170 jts 2-7/8" production tbg. GIH w/bit & scraper to PBTD 5486'. COOH & LD bit & scraper and GIH w/7" Model R pkr, set at 5359'. Spearheaded 300 gal xylene & acidized w/5000 gal 15% MSR-100, diverted in 3 stages w/1500 gal WF-30 with 3#/gal medium rock salt, displaced w/35 bbls wtr. Shut well in for 2 hrs. Swabbed well. COOH w/pkr & GIH w/production tbg. Set TAC at 5296' and SN at 5485'. ND BOP, NU WH. Ran rods & pump. RD & MO well service unit and returned well to production 7/20/90.

Test Prior to Acid Job - 57 BOPD, 0 BWPD, 10 MCFGPD
Test After Acid Job - 74 BOPD, 6 BWPD, 13 MCFGPD

Distribution:

5 - BLM, Farmington 1 - S. H. Oden 1 - Chevron
2 - Utah O&GCC 1 - P. J. Konkel 1 - PPCo, Houston
1 - EPA, Denver 1 - Chieftain 1 - PPCo, Cortez, RC
1 - N. Anstine 1 - Mobil Oil
1 - V. S. Shaw 1 - Texaco, Inc.

14. I hereby certify that the foregoing is true and correct

Signed S. H. Oden S. H. Oden Title District Superintendent Date August 2, 1990

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

Page 1 of 10

MONTHLY OIL AND GAS PRODUCTION REPORT

OPERATOR NAME AND ADDRESS:

P J KONKEL
PHILLIPS PETROLEUM COMPANY
5525 HWY 64 NBU 3004
FARMINGTON NM 87401

RECEIVED

AUG 16 1993

DIVISION OF
OIL, GAS & MINING

ACCOUNT NUMBER: N0772

REPORT PERIOD (MONTH/YEAR):

6 / 93

AMENDED REPORT ☐ (Highlight Changes)

Well Name					Producing Zone	Well Status	Days Oper	Production Volumes		
API Number	Entity	Location						OIL(BBL)	GAS(MCF)	WATER(BBL)
#21-23										
4303713754	06280	41S	24E	21	DSCR	POW	29	1374	883	58
#3-44										
4303715031	06280	41S	24E	3	DSCR	POW	30	111	94	2905
#3-14										
4303715124	06280	41S	24E	3	DSCR	POW	30	67	23	302
#9-12										
4303715126	06280	41S	24E	9	DSCR	POW	30	112	654	17363
#9-14										
4303715127	06280	41S	24E	9	DSCR	POW	30	201	315	423
#28-12										
4303715336	06280	41S	24E	28	PRDX	POW	29	112	47	2428
#29-12										
4303715337	06280	41S	24E	29	PRDX	POW	29	56	0	672
#29-32										
4303715339	06280	41S	24E	29	DSCR	POW	29	1402	287	2224
#29-34										
4303715340	06280	41S	24E	29	DSCR	POW	29	757	48	0
#30-32										
4303715342	06280	41S	24E	30	DSCR	POW	29	588	1049	3744
#3-12										
4303715620	06280	41S	24E	3	DSCR	POW	30	268	11	363
#9-34										
4303715711	06280	41S	24E	9	DSCR	POW	30	45	46	9800
#10-12										
4303715712	06280	41S	24E	10	DSCR	POW	30	45	23	1088
TOTALS								5138	3480	41370

COMMENTS: Effective July 1, 1993, Phillips Petroleum Company has sold its interest in the
Ratherford Unit to Mobil Exploration and Producing U.S., Incorporated, P. O. Box
633, Midland, Texas 79702. Mobil assumed operations on July 1, 1993.

I hereby certify that this report is true and complete to the best of my knowledge.

Date: 8/11/93

Name and Signature: PAT KONKEL

Pat Konkell

Telephone Number: 505 599-3452

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS <small>(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)</small>		5. LEASE DESIGNATION & SERIAL NO. 6. IF INDIAN, ALLOTTEE OR TRIBE NAME NAVAJO TRIBAL	
1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		7. UNIT AGREEMENT NAME RATHERFORD UNIT	
2. NAME OF OPERATOR MOBIL OIL CORPORATION		8. FARM OR LEASE NAME	
3. ADDRESS OF OPERATOR P. O. BOX 633 MIDLAND, TX 79702		9. WELL NO.	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface At proposed prod. zone		10. FIELD AND POOL, OR WILDCAT GREATER ANETH	
14. API NO.		15. ELEVATIONS (Show whether DF, RT, GR, etc.)	
12. COUNTY SAN JUAN		13. STATE UTAH	

16. Check Appropriate Box To Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) <u>CHANGE OF OPERATOR</u> <input type="checkbox"/>	
(Other) <input type="checkbox"/>		(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	
APPROX. DATE WORK WILL START _____		DATE OF COMPLETION _____	

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

* Must be accompanied by a cement verification report.

AS OF JULY1, 1993, MOBIL OIL CORPORATION IS THE OPERATOR OF THE RATHERFORD UNIT.
ATTACHED ARE THE INDIVIDUAL WELLS.

18. I hereby certify that the foregoing is true and correct.

SIGNED <u>Shirley Todd</u>	TITLE <u>ENV. & REG TECHNICIAN</u>	DATE <u>9-8-93</u>
(This space for Federal or State Office use)		
APPROVED BY _____	TITLE _____	DATE _____
CONDITIONS OF APPROVAL, IF ANY:		

See Instructions On Reverse Side

STATE OF UTAH
DIVISION OF OIL, GAS AND MININGPage 1 of 1

MONTHLY OIL AND GAS DISPOSITION REPORT

OPERATOR NAME AND ADDRESS:

L B Sheffield~~BRIAN BERRY~~~~M E P N A MOBIL~~~~POB 219031 1807A RENTWY~~ *P.O. DRAWER 6*~~DALLAS TX 75221-9031~~ *CORTEZ, CO. 81321*UTAH ACCOUNT NUMBER: N7370REPORT PERIOD (MONTH/YEAR): 7 / 93AMENDED REPORT ☐ (Highlight Changes)*X931006 updated. Jee*

ENTITY NUMBER	PRODUCT	GRAVITY	BEGINNING INVENTORY	VOLUME PRODUCED	DISPOSITIONS				ENDING INVENTORY
		BTU			TRANSPORTED	USED ON SITE	FLARED/VENTED	OTHER	
05980	OIL			177609	177609	0			
	GAS			72101	66216	5885			
11174	OIL								
	GAS								
	OIL								
	GAS								
	OIL								
	GAS								
	OIL								
	GAS								
	OIL								
	GAS								
	OIL								
	GAS								
	OIL								
	GAS								
TOTALS				249710	243825	5885			

COMMENTS:

*PLEASE NOTE ADDRESS change. Mobil ~~ASCO~~ PRODUCTION REPORTS
will be compiled and sent from the Cortez, Co. office
IN THE FUTURE.*

I hereby certify that this report is true and complete to the best of my knowledge.

Name and Signature:

Lwell B Sheffield

Date:

9/5/93

Telephone Number:

*303 565 2212
244 658 2528*

Sept 29, 1993

TO: Lisha Cordova - Utah Mining
Oil & Gas

FROM: Janice Easley
BLM Farmington, NM
505 599-6355

Here is copy of Rutherford Unit
Successor Operator.

4 pages including this one.

File Rotherford Unit (GC)

RECEIVED
BLM

JUL 27 AM 11:44

070 FARMINGTON, NM

Navajo Area Office
P. O. Box 1060
Gallup, New Mexico 87305-1060

ARES/543

JUL 26 1993


Mr. G. D. Cox
Mobil Exploration and
Producing North America, Inc.
P. O. Box 633
Midland, Texas 79702

Dear Mr. Cox:

Enclosed for your information and use is the approved Designation of Operator between the Phillips Petroleum Company and Mobil Exploration and Producing North America, Inc. for the Rotherford Unit.

Please note that all other concerned parties will be furnished their copy of the approved document.

Sincerely,



ACTING Area Director

Enclosure

cc: Bureau of Land Management, Farmington District Office w/enc.
TNN, Director, Minerals Department w/enc.

MINERALS DIVISION
1993
JUL 26 1993
3
ALL SUPPLY
FILE

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF INDIAN AFFAIRS

RECEIVED
BLM

DESIGNATION OF OPERATOR

Phillips Petroleum Company is, on the records of the Bureau of Indian Affairs, operator of the Ratherford Unit, ^{62 JUN 27 1993}

AREA OFFICE: Window Rock, Arizona
LEASE NO: Attached hereto as Exhibit "A"

070 FARMINGTON, NM

and, pursuant to the terms of the Ratherford Unit Agreement, is resigning as Unit Operator effective July 1, 1993, and hereby designates

NAME: Mobil Exploration and Producing North America Inc., duly elected pursuant to the terms of the Ratherford Unit Agreement,

ADDRESS: P. O. Box 633, Midland, Texas 79702
Attn: G. D. Cox

as Operator and local agent, with full authority to act on behalf of the Ratherford Unit lessees in complying with the terms of all leases and regulations applicable thereto and on whom the authorized officer may serve written or oral instructions in securing compliance with the Operating Regulations (43 CFR 3160 and 25 CFR 211 and 212) with respect to (described acreage to which this designation is applicable):

Attached hereto as Exhibit "A"

Bond coverage under 25 CFR 211, 212 or 225 for lease activities conducted by the above named designated operator is under Bond Number 05202782 (attach copy). Evidence of bonding is required prior to the commencement of operations.

It is understood that this designation of operator does not relieve any lessee of responsibility for compliance with the terms of the leases and the Operating Regulations. It is also understood that this designation of operator does not constitute an assignment of any interest in the leases.

In case of default on the part of the designated operator, the lessees will make full and prompt compliance with all regulations, lease terms, stipulations, or orders of the Secretary of the Interior or his representative.

Attached is the appropriate documentation relevant to this document.

The designated operator agrees to promptly notify the authorized officer of any change in the operatorship of said Ratherford Unit.

Phillips Petroleum Company

June 17, 1993

By: M. B. [Signature]
Attorney-in-Fact

Mobil Exploration and Producing
North America Inc.

June 11, 1993

By: B. D. Martiny
Attorney-in-Fact B.D. MARTINY

[Signature] ACTING AREA DIRECTOR
APPROVED BY TITLE DATE 7/9/93

APPROVED PURSUANT, TO SECRETARIAL REDELEGATION ORDER 209 DM 8 AND 230 DM 3.

This form does not constitute an information collection as defined by 44 U.S.C. 3502 and therefore does not require OMB approval.

EXHIBIT "A"

ATTACHED TO AND MADE A PART OF DESIGNATION OF SUCCESSOR OPERATOR, RATHERFORD UNIT

EXHIBIT "C"

Revised as of September 29, 1992
SCHEDULE OF TPACT PERCENTAGE PARTICIPATION

<u>Tract Number</u>	<u>Description of Land</u>	<u>Serial Number and Effective Date of Lease</u>	<u>Tract Percentage Participation</u>
1	S/2 Sec. 1, E/2 SE/4 Sec. 2, E/4 Sec. 11, and all of Sec. 12, T-41-S, R-23-E, S.L.M. San Juan County, Utah	14-20-603-246-A Oct. 5, 1953	11.0652565
2	SE/4 and W/2 SW/4 Sec. 5, the irregular SW/4 Sec. 6, and all of Sec. 7 and 8, T-41-S, R-24-E, San Juan County, Utah	14-20-603-368 Oct. 26, 1953	14.4159942
3	SW/4 of Sec. 4, T-41-S, R-24-E, San Juan County, Utah	14-20-603-5446 Sept. 1, 1959	.5763826
4	SE/4 Sec. 4, and NE/4 Sec. 9, T-41-S, R-24-E, San Juan County, Utah	14-20-603-4035 March 3, 1958	1.2587779
5	SW/4 of Sec. 3, T-41-S, R-24-E, S.L.M., San Juan County, Utah	14-20-603-5445 Sept. 3, 1959	.4667669
6	NW/4 of Sec. 9, T-41-S, R-24-E, S.L.M., San Juan County, Utah	14-20-603-5045 Feb. 4, 1959	1.0187043
7	NW/4, W/2 NE/4, and SW/4 Sec. 10, SE/4 Sec. 9, T-41-S, R-24-E, San Juan County, Utah	14-20-603-4043 Feb. 18, 1958	3.5097575
8	SW/4 Sec. 9, T-41-S, R-24-E, S.L.M. San Juan County, Utah	14-20-603-5046 Feb. 4, 1959	1.1141679
9	SE/4 Sec. 10 and S/2 SW/4 Sec. 11 T-41-S, R-24-E, San Juan County, Utah	14-20-603-4037 Feb. 14, 1958	2.6186804
10	All of Sec. 13, E/2 Sec. 14, and E/2 SE/4 and N/2 Sec. 24, T-41-S, R-23-E, S.L.M., San Juan County, Utah	14-20-603-247-A Oct. 5, 1953	10.3108861
11	Sections 17, 18, 19 and 20, T-41-S, R-24-E, San Juan County Utah	14-20-603-353 Oct. 27, 1953	27.3389265
12	Sections 15, 16, 21, and NW/4, and W/2 SW/4 Sec. 22, T-41-S, R-24-E, San Juan County, Utah	14-20-603-355 Oct. 27, 1953	14.2819339
13	W/2 Section 14, T-41-S, R-24-E, San Juan County, Utah	14-20-603-370 Oct. 26, 1953	1.8500847
14	N/2 and SE/4, and E/2 SW/4 Sec. 29, NE/4 and E/2 SE/4 and E/2 W/2 irregular Sec. 30, and E/2 NE/4 Sec. 32, T-41-S, R-24-E, San Juan County, Utah	14-20-603-407 Dec. 10, 1953	6.9924969
15	NW/4 Sec. 28, T-41-S, R24-E San Juan County, Utah	14-20-603-409 Dec. 10, 1953	.9416393
16	SE/4 Sec. 3, T-41-S, R-24-E San Juan County, Utah	14-20-0603-6504 July 11, 1961	.5750254
17	NE/4 Sec. 3, T-41-S, R-24-E San Juan County, Utah	14-20-0603-6505 July 11, 1961	.5449292
18	NW/4 Sec. 3, T-41-S, R-24-E San Juan County, Utah	14-20-0603-6506 July 11, 1961	.5482788
19	NE/4 Sec. 4, T-41-S, R24-E San Juan County, Utah	14-20-0603-7171 June 11, 1962	.4720628
20	E/2 NW/4 Sec. 4, T-41-S, R-24-E San Juan County, Utah	14-20-0603-7172 June 11, 1962	.0992482

100% Indian Lands

TOTAL 12,909.74

100.0000000

PHONE CONVERSATION DOCUMENTATION FORM

Route original/copy to:

☐ Well File _____☐ Suspense☒ Other

(Return Date) _____

OPERATOR CHANGE

(Location) Sec _____ Twp _____ Rng _____

(To - Initials) _____

(API No.) _____

1. Date of Phone Call: 10-6-93 : Time: 9:302. DOGM Employee (name) L. CORDOVA (Initiated Call ☒
Talked to:Name GLEN COX (Initiated Call ☐ - Phone No. (915) 688-2114of (Company/Organization) MOBIL3. Topic of Conversation: OPERATOR CHANGE FROM PHILLIPS TO MOBIL "RATHERFORD UNIT".(NEED TO CONFIRM HOW OPERATOR WANTS THE WELLS SET UP - MEPNA AS PER BIA APPROVALOR MOBIL OIL CORPORATION AS PER SUNDRY DATED 9-8-93?)

4. Highlights of Conversation: _____

MR. COX CONFIRMED THAT THE WELLS SHOULD BE SET UNDER ACCOUNT N7370/MEPNA ASPER BIA APPROVAL, ALSO CONFIRMED THAT PRODUCTION & DISPOSITION REPORTS WILL NOWBE HANDLED OUT OF THEIR CORTEZ OFFICE RATHER THAN DALLAS.MEPNA-PO DRAWER GCORTEZ, CO 81321(303)565-2212*ADDRESS CHANGE AFFECTS ALL WELLS CURRENTLY OPERATED BY MEPNA, CURRENTLYREPORTED OUT OF DALLAS (MCELMO CREEK).

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

Routing:

1-VLC/7-93
2-DTS/8-93
3-VLC
4-RJE
5-DEC
6-PL

Attach all documentation received by the division regarding this change.
 Initial each listed item when completed. Write N/A if item is not applicable.

- ☒ Change of Operator (well sold) ☐ Designation of Agent
☐ Designation of Operator ☐ Operator Name Change Only

The operator of the well(s) listed below has changed (EFFECTIVE DATE: 7-1-93)

TO (new operator) <u>M E P N A</u>	FROM (former operator) <u>PHILLIPS PETROLEUM COMPANY</u>
(address) <u>PO DRAWER G</u>	(address) <u>5525 HWY 64 NBU 3004</u>
<u>CORTEZ, CO 81321</u>	<u>FARMINGTON, NM 87401</u>
<u>GLEN COX (915) 688-2114</u>	<u>PAT KONKEL</u>
phone <u>(303) 565-2212</u>	phone <u>(505) 599-3452</u>
account no. <u>N7370</u>	account no. <u>N0772(A)</u>

Well(s) (attach additional page if needed):

***RATHERFORD UNIT (NAVAJO)**

Name: **SEE ATTACHED**	API: <u>43037-31080</u>	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____

OPERATOR CHANGE DOCUMENTATION

- See 1. (Rule R615-8-10) Sundry or other legal documentation has been received from former operator (Attach to this form). (Reg. 8-20-93) (6/93 Prod. Rpt. 8-16-93)
- See 2. (Rule R615-8-10) Sundry or other legal documentation has been received from new operator (Attach to this form). (Reg. 8-31-93) (Rec'd 9-14-93)
- N/A 3. The Department of Commerce has been contacted if the new operator above is not currently operating any wells in Utah. Is company registered with the state? (yes/no) ____ If yes, show company file number: _____.
- See 4. (For Indian and Federal Wells ONLY) The BLM has been contacted regarding this change (attach Telephone Documentation Form to this report). Make note of BLM status in comments section of this form. Management review of Federal and Indian well operator changes should take place prior to completion of steps 5 through 9 below.
- See 5. Changes have been entered in the Oil and Gas Information System (Wang/IBM) for each well listed above. (O&G wells 10-6-93) (Wiw's 10-26-93)
- See 6. Cardex file has been updated for each well listed above. (O&G wells 10-6-93) (Wiw's 10-26-93)
- See 7. Well file labels have been updated for each well listed above. (O&G wells 10-6-93) (Wiw's 10-26-93)
- See 8. Changes have been included on the monthly "Operator, Address, and Account Changes" memo for distribution to State Lands and the Tax Commission. (10-6-93)
- See 9. A folder has been set up for the Operator Change file, and a copy of this page has been placed there for reference during routing and processing of the original documents.

ENTITY REVIEW

- ☒ 1. (Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/no) no (If entity assignments were changed, attach copies of Form 6, Entity Action Form).
- ☒ 2. State Lands and the Tax Commission have been notified through normal procedures of entity changes.

BOND VERIFICATION (Fee wells only)

- ☒ 1. (Rule R615-3-1) The new operator of any fee lease well listed above has furnished a proper bond.
- ☐ 2. A copy of this form has been placed in the new and former operators' bond files.
- ☐ 3. The former operator has requested a release of liability from their bond (yes/no) _____. Today's date _____ 19____. If yes, division response was made by letter dated _____ 19____.

LEASE INTEREST OWNER NOTIFICATION RESPONSIBILITY

- ☒ 1. (Rule R615-2-10) The former operator/lessee of any fee lease well listed above has been notified by letter dated _____ 19____, of their responsibility to notify any person with an interest in such lease of the change of operator. Documentation of such notification has been requested.
- ☒ 2. Copies of documents have been sent to State Lands for changes involving State leases.

FILMING

- ☒ 1. All attachments to this form have been microfilmed. Date: 11-17 19 93.

FILING

- ☒ 1. Copies of all attachments to this form have been filed in each well file.
- ☒ 2. The original of this form and the original attachments have been filed in the Operator Change file.

COMMENTS

931006 BIA/Bhm Approved 7-9-93.

12W-44	43-037-16405	14-20-603-246A	SEC. 12, T41S, R23E	SE/SE 660 FSL; 660 FEL	PA'd
12W-44A	43-037-31543	14-20-603-246A	SEC. 12, T41S, R23E	SE/SE 807 FEL; 772 FSL	
13-11W	43-037-31152	14-20-603-247A	SEC. 13, T41S, R23E	NW/NW 500 FNL; 660 FWL	
13-12	43-037-31127	14-20-603-247A	SEC. 13, T41S, R23E	SW/NW 1705 FNL; 640 FWL	
13W-13	43-037-15851	14-20-603-247A	SEC. 13, T41S, R23E	NW/SW 1980 FSL; 4620 FEL	
13-14	43-037-31589	14-20-603-247A	SEC. 13, T41S, R23E	660 FSL; 660 FWL	
13-21	43-037-31128	14-20-603-247A	SEC. 13, T41S, R23E	NE/NW 660 FNL; 1920 FWL	
13W-22	43-037-15852	14-20-603-247A	SEC. 13, T41S, R23E	SE/NW 1988 FNL; 3300 FEL	
13-23	43-037-31129	14-20-603-247A	SEC. 13, T41S, R23E	NE/SW 1980 FSL; 1930 FWL	
13W-44	43-037-15853	14-20-603-247	SEC. 13, T41S, R23E	600 FSL; 3300 FEL	
13W-32	43-037-16406	14-20-603-247A	SEC. 13, T41S, R23E	1881 FNL; 1979 FEL	
13W-33	43-037-15855	14-20-603-247A	SEC. 13, T41S, R23E	NW/SE 1970 FSL; 1979 FEL	
13W-34	43-037-31130	14-20-603-247A	SEC. 13, T41S, R23E	SW/SE 660 FSL; 1980 FEL	
13-41	43-037-15856	14-20-603-247A	SEC. 13, T41S, R23E	NE/NE 660 FNL; 660 FEL	
13W-42	43-037-15857	14-20-603-247A	SEC. 13, T41S, R23E	SE/NE 2139; 585 FEL	
13-43	43-037-31131	14-20-603-247A	SEC. 13, T41S, R23E	NE/SE 1700 FSL; 960 FEL	
13W-44	43-037-16407	14-20-603-247A	SEC. 13, T41S, R23E	SE/SE 635 FSL; 659 FEL	
14-02	NA	14-20-603-4037	SEC. 11, T41S, R23E	SW/SW 660 FSL; 660 FEL	
14-32	43-037-15858	14-20-603-247A	SEC. 14, T41S, R23E	2130 FNL; 1830 FEL	
14-41	43-037-31623	14-20-603-247A	SEC. 14, T41S, R23E	NE/NE 521 FEL; 810 FNL	
14W-42	43-037-15860	14-20-603-247A	SEC. 14, T41S, R23E	SE/NE 1976 FNL; 653 FEL	
14W-43	43-037-16410	14-20-603-247A	SEC. 14, T41S, R23E	3300 FSL; 4770 FEL	
14-33	43-037-15859	14-20-603-247	SEC. 14, T41S, R23E	2130 FSL; 1830 FEL	
15-12	43-037-15715	14-20-603-355	SEC. 15, T41S, R24E	1820 FNL; 500 FWL	
15W-21	43-037-16411	14-20-603-355	SEC. 15, T41S, R24E	660 FNL; 1820 FWL	
15-22	43-037-30449	14-20-603-355	SEC. 15, T41S, R24E	SE/NW, 1980 FNL; 2050 FWL	
15-32	43-037-15717	14-20-603-355A	SEC. 15, T41S, R24E	1980 FNL; 1980 FEL	
15-33	43-037-15718	14-20-603-355	SEC. 15, T41S, R24E	NW/SE 1650 FSL; 1980 FEL	
15-41	43-037-15719	14-20-603-355	SEC. 15, T41S, R24E	660 FNL; 660' FEL	
15-42	43-037-30448	14-20-603-355	SEC. 15, T41S, R24E	SE/NE 2020 FNL; 820 FEL	
16W-12	43-037-15720	14-20-603-355	SEC. 16, T41S, R24E	SW/NW 1880 FNL; 660 FWL	
16-13	43-037-31168	14-20-603-355	SEC. 16, T41S, R24E	1980 FSL; 660 FWL	
16W-14	43-037-15721	14-20-603-355	SEC. 16, T41S, R24E	SW/SW 660 FSL; 660 FWL	
16W-21	43-037-16414	14-20-603-355	SEC. 16, T41S, R24E	NE/NW 660 FNL; 1880 FWL	
16W-23	43-037-15722	14-20-603-355	SEC. 16, T41S, R24E	NE/SW 1980 FSL; 1980 FWL	
16-32	43-037-15723	14-20-603-355	SEC. 16, T41S, R24E	1980 FNL; 1980' FEL	
16-34	43-037-15724	14-20-603-355	SEC. 16, T41S, R24E	660 FNL; 1980' FEL	
16-41	43-037-15725	14-20-603-355	SEC. 16, T41S, R24E	660 FNL; 660 FEL	
16W-43	43-037-16415	14-20-603-355	SEC. 16, T41S, R24E	NE/SE 2140 FSL; 820 FEL	
17-11	43-037-31169	14-20-603-353	SEC. 17, T41S, R24E	NW/NW 1075' FNL; 800' FWL	
17W-12	43-037-15726	14-20-603-353	SEC. 17, T41S, R24E	SW/NW 1980' FNL; 510' FWL	
17-13	43-037-31133	14-20-603-353	SEC. 17, T41S, R24E	NW/SW 2100' FSL; 660' FWL	
17W-14	43-037-15727	14-20-603-353	SEC. 17, T41S, R24E	SW/SW 660' FSL; 660' FWL	
17W-21	43-037-16416	14-20-603-353	SEC. 17, T41S, R24E	510' FNL; 1830' FWL	
17-22	43-037-31170	14-20-603-353	SEC. 17, T41S, R24E	1980' FNL; 1980' FWL	
17W-23	43-037-15728	14-20-603-353	SEC. 17, T41S, R24E	NE/SW 1980' FWL; 1880' FSL	
17-31	43-037-31178	14-20-603-353	SEC. 17, T41S, R24E	NW/NE 500' FNL; 1980' FEL	
17-32W	43-037-15729	14-20-603-353	SEC. 17, T41S, R24E	SW/NE 1830' FNL; 2030' FEL	
17-33	43-037-31134	14-20-603-353	SEC. 17, T41S, R24E	NW/SE 1980' FSL; 1845' FEL	
17-34W	43-037-15730	14-20-603-353	SEC. 17, T41S, R24E	SW/SE 560' FSL; 1880' FEL	
17W-41	43-037-15731	14-20-603-353	SEC. 17, T41S, R24E	610' FNL; 510' FEL	
17-42	43-037-31177	14-20-603-353	SEC. 17, T41S, R24E	SE/NE 1980; FNL, 660' FEL	
17-44	43-037-15732	14-20-603-353	SEC. 17, T41S, R24E	660 FSL; 660' FEL	
17W-43	43-037-16417	14-20-603-353	SEC. 17, T41S, R24E	NE/SE 1980' FSL; 660' FEL	
18-11	43-037-15733	14-20-603-353	SEC. 18, T41S, R24E	NW/NW 720' FNL; 730' FWL	
18-12W	43-037-31153	14-20-603-353	SEC. 18, T41S, R24E	SW/NW 1980' FNL; 560' FWL	
18W-21	43-037-16418	14-20-603-353	SEC. 18, T41S, R24E	NE/NW 660' FNL; 1882' FWL	
18-22	43-037-31236	14-20-603-353	SEC. 18, T41S, R24E	SW/NW 2200' FNL; 2210' FWL	
18W-23	43-037-30244	14-20-603-353	SEC. 18, T41S, R24E	NE/SW 2385' FSL; 2040' FWL	
18W-14	43-037-15735	14-20-603-353	SEC. 18, T41S, R24E	SW/SW 810' FSL; 600' FWL	
18-24	43-037-31079	14-20-603-353	SEC. 18, T41S, R24E	SE/SW 760' FSL; 1980' FWL	
18-31	43-037-31181	14-20-603-353	SEC. 18, T41S, R24E	NW/NE 795' FNL; 2090; FEL	
18W-32	43-037-15736	14-20-603-353	SEC. 18, T41S, R24E	SW/NE 2140' FNL; 1830' FEL	
18-33	43-037-31135	14-20-603-353	SEC. 18, T41S, R24E	NW/SE 1870' FSL; 1980' FEL	
18-34W	43-037-15737	14-20-603-353	SEC. 18, T41S, R24E	SW/SE 780' FSL; 1860 FEL	
18W-41	43-037-15738	14-20-603-353	SEC. 18, T41S, R24E	NE/NE 660' FNL; 660' FEL	
18-42	43-037-31182	14-20-603-353	SEC. 18, T41S, R24E	SE/NE 2120' FNL; 745' FEL	
18W-43	43-037-16419	14-20-603-353	SEC. 18, T41S, R24E	NE/SE 1980' FSL; 660' FEL	PA'd
18-44	43-037-31045	14-20-603-353	SEC. 18, T41S, R24E	SE/SE 660' FSL; 660' FEL	
19-11	43-037-31080	14-20-603-353	SEC. 19, T41S, R24E	NW/NW 660' FNL; 660' FWL	
19-12	43-037-15739	14-20-603-353	SEC. 19, T41S, R24E	600' FWL; 1980' FNL	
19-14	43-037-15740	14-20-603-353	SEC. 19, T41S, R24E	600' FSL; 660' FEL	

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
 355 West North Temple, 3 Triad, Suite 350, Salt Lake City, UT 84180-1203

Page 19 of 22

MONTHLY OIL AND GAS PRODUCTION REPORT

OPERATOR NAME AND ADDRESS:

C/O MOBIL OIL CORP
 M E P N A
 PO DRAWER G
 CORTEZ CO 81321

UTAH ACCOUNT NUMBER: N7370

REPORT PERIOD (MONTH/YEAR): 6 / 95

AMENDED REPORT ☐ (Highlight Changes)

Well Name						Producing Zone	Well Status	Days Oper	Production Volumes		
API Number	Entity		Location		OIL(BBL)				GAS(MCF)	WATER(BBL)	
RATHERFORD UNIT 20-31						ISMV					
4303731050	06280	41S	24E	20							
RATHERFORD UNIT 20-42						DSCR					
4303731051	06280	41S	24E	20							
RATHERFORD UNIT 21-11						DSCR					
4303731052	06280	41S	24E	21							
RATHERFORD UNIT 29-11						DSCR					
4303731053	06280	41S	24E	29							
RATHERFORD UNIT #18-24						DSCR					
4303731079	06280	41S	24E	18							
RATHERFORD UNIT #19-11						DSCR					
4303731080	06280	41S	24E	19							
RATHERFORD UNIT #19-44						DSCR					
4303731081	06280	41S	24E	19							
RATHERFORD UNIT #29-22						DSCR					
4303731082	06280	41S	24E	29							
RATHERFORD UNIT 12-34						DSCR					
4303731126	06280	41S	23E	12							
RATHERFORD UNIT 13-12						DSCR					
4303731127	06280	41S	23E	13							
RATHERFORD UNIT #13-21						DSCR					
4303731128	06280	41S	23E	13							
RATHERFORD UNIT #13-23						DSCR					
4303731129	06280	41S	23E	13							
RATHERFORD UNIT 13-34 (RE-ENTRY)						DSCR					
4303731130	06280	41S	23E	13							
TOTALS											

REMARKS: _____

I hereby certify that this report is true and complete to the best of my knowledge.

Date: _____

Name and Signature: _____

Telephone Number: _____

PHONE CONVERSATION DOCUMENTATION FORM

Route original/copy to:

☐ **Well File** _____
 (Location) Sec _____ Twp _____ Rng _____
 (API No.) _____

☐ **Suspense** _____
 (Return Date) _____
 (To - Initials) _____

☒ **Other** _____
OPER NM CHG _____

1. Date of Phone Call: 8-3-95 Time: _____

2. DOGM Employee (name) L. CORDOVA (Initiated Call ☐)
 Talked to:

Name R. J. FIRTH (Initiated Call ☒) - Phone No. (_____) _____
 of (Company/Organization) _____

3. Topic of Conversation: M E P N A / N7370

4. Highlights of Conversation: _____

OPERATOR NAME IS BEING CHANGED FROM M E P N A (MOBIL EXPLORATION AND PRODUCING
NORTH AMERICA INC) TO MOBIL EXPLOR & PROD. THE NAME CHANGE IS BEING DONE AT
THIS TIME TO ALLEVIATE CONFUSION, BOTH IN HOUSE AND AMONGST THE GENERAL PUBLIC.
*SUPERIOR OIL COMPANY MERGED INTO M E P N A 4-24-86 (SEE ATTACHED).

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

Routing:

1-LEC	7-PL
2-LWP	8-SJ
3-DEC	9-FILE
4-VLC	
5-RJP	
6-LWP	

Attach all documentation received by the division regarding this change.
 Initial each listed item when completed. Write N/A if item is not applicable.

- ☐ Change of Operator (well sold) ☐ Designation of Agent
☐ Designation of Operator ☒ Operator Name Change Only

The operator of the well(s) listed below has changed (EFFECTIVE DATE: 8-2-95)

TO (new operator) MOBIL EXPLOR & PROD
 (address) C/O MOBIL OIL CORP
PO DRAWER G
CORTEZ CO 81321
 phone (303) 564-5212
 account no. N7370

FROM (former operator) M E P N A
 (address) C/O MOBIL OIL CORP
PO DRAWER G
CORTEZ CO 81321
 phone (303) 564-5212
 account no. N7370

Well(s) (attach additional page if needed):

Name: ** SEE ATTACHED **	API: <u>C37-31080</u>	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____

OPERATOR CHANGE DOCUMENTATION

- N/A 1. (Rule R615-8-10) Sundry or other legal documentation has been received from former operator (Attach to this form).
- N/A 2. (Rule R615-8-10) Sundry or other legal documentation has been received from new operator (Attach to this form).
- N/A 3. The Department of Commerce has been contacted if the new operator above is not currently operating any wells in Utah. Is company registered with the state? (yes/no) ____ If yes, show company file number: _____.
- N/A 4. (For Indian and Federal Wells ONLY) The BLM has been contacted regarding this change (attach Telephone Documentation Form to this report). Make note of BLM status in comments section of this form. Management review of **Federal and Indian** well operator changes should take place prior to completion of steps 5 through 9 below.
- Lee 5. Changes have been entered in the Oil and Gas Information System (Wang/IBM) for each well listed above. (8-3-95)
- LWP 6. Cardex file has been updated for each well listed above. 8-21-95
- LWP 7. Well file labels have been updated for each well listed above. 9-28-95
- Lee 8. Changes have been included on the monthly "Operator, Address, and Account Changes" memo for distribution to State Lands and the Tax Commission. (8-3-95)
- Lee 9. A folder has been set up for the Operator Change file, and a copy of this page has been placed there for reference during routing and processing of the original documents.

ENTITY REVIEW

- Yes 1. (Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/no) no (If entity assignments were changed, attach copies of Form 6, Entity Action Form).
- N/A 2. State Lands and the Tax Commission have been notified through normal procedures of entity changes.

BOND VERIFICATION (Fee wells only) ** No Fee Lease Wells at this time!*

- N/A Yes 1. (Rule R615-3-1) The new operator of any fee lease well listed above has furnished a proper bond.
2. A copy of this form has been placed in the new and former operators' bond files.
3. The former operator has requested a release of liability from their bond (yes/no) . Today's date 19 . If yes, division response was made by letter dated 19 .

LEASE INTEREST OWNER NOTIFICATION RESPONSIBILITY

- N/A 1. (Rule R615-2-10) The former operator/lessee of any **fee lease** well listed above has been notified by letter dated 19 , of their responsibility to notify any person with an interest in such lease of the change of operator. Documentation of such notification has been requested.
- N/A 2. Copies of documents have been sent to State Lands for changes involving **State leases**.

FILMING

- ✓ 1. All attachments to this form have been microfilmed. Date: October 6 1995.

FILING

1. Copies of all attachments to this form have been filed in each well file.
2. The original of this form and the original attachments have been filed in the Operator Change file.

COMMENTS

950803 UIC F5/Not necessary!

ExxonMobil Production Company
U.S. West
P.O. Box 4358
Houston, Texas 77210-4358

June 27, 2001

ExxonMobil
Production

Mr. Jim Thompson
State of Utah, Division of Oil, Gas and Mining
1549 West North Temple
Suite 1210
Salt Lake City, UT 84114-5801

Change of Name – Mobil Oil Corporation to
ExxonMobil Oil Corporation

Dear Mr. Thompson

Effective June 1, 2001, Mobil Oil Corporation (MOC) changed its name to ExxonMobil Oil Corporation (EMOC). This was a name change only; EMOC is the same corporation as Mobil Oil Corporation, but with a new name. No facility or other asset was transferred from one corporation to another by virtue of the name change. Specifically, EMOC will remain the owner and operator of its existing exploration and production oil and gas properties and facilities, as well as relevant permits.

There is no change to the name of Exxon Mobil Corporation, the ultimate shareholder of EMOC.


Please note the change of name of MOC to ExxonMobil Oil Corporation in your records pertaining to any MOC permits.

The Federal Identification Number for MOC (13-5401570) will remain the same for EMOC.

A copy of the Certification, Bond Rider and a list of wells are attached.

If you have any questions please feel free to call Joel Talavera at 713-431-1010

Very truly yours,



Charlotte H. Harper
Permitting Supervisor

ExxonMobil Production Company
a division of Exxon Mobil Corporation,
acting for ExxonMobil Oil Corporation

RECEIVED

JUN 29 2001

DIVISION OF
OIL, GAS AND MINING



IN REPLY REFER TO:

United States Department of the Interior

BUREAU OF INDIAN AFFAIRS
~~XXXXXXXXXXXX~~
Navajo Area Office
NAVAJO REGIONP.O. Box 1060
Gallup, New Mexico 87305-1060

AUG 30 2001

RRES/543

CERTIFIED MAIL - RETURN RECEIPT REQUESTEDCharlotte H. Harper, Permitting Supervisor
Exxon Mobil Production Company
U. S. West
P. O. Box 4358
Houston, TX 77210-4358

Dear Ms. Harper:

This is to acknowledge receipt of your company's name change from Mobil Oil Corporation to ExxonMobil Oil Corporation effective June 1, 2001. The receipt of documents includes the Name Change Certification, current listing of Officers and Directors, Listing of Leases, Financial Statement, filing fees of \$75.00 and a copy of the Rider for Bond Number 8027 31 97. There are no other changes.

Please note that we will provide copies of these documents to other concerned parties. If you need further assistance, you may contact Ms. Bertha Spencer, Realty Specialist, at (928) 871-5938.

Sincerely,

DENNETT DENETSONE

Regional Realty Officer

cc: BLM, Farmington Field Office w/enclosures ✓
Navajo Nation Minerals Office, Attn: Mr. Akhtar Zaman, Director/w enclosures

MINERAL RESOURCES	
ADM 1	<i>DB/MC</i>
NATV AM MIN COORD	
SOLID MIN TEAM	
PETRO MIN TEAM <i>2</i>	
O & G INSPECT TEAM	
ALL TEAM LEADERS	
LAND RESOURCES	
ENVIRONMENT	
FILES	

ExxonMobil Production Company
U.S. West
P.O. Box 4358
Houston, Texas 77210-4358


ps 7/12/01
SH
543
File

June 27, 2001

ExxonMobil
Production

Certified Mail
Return Receipt Requested

Ms. Genni Denetsone
United States Department of the Interior
Bureau of Indian Affairs, Navajo Region
Real Estate Services
P. O. Box 1060
Gallup, New Mexico 87305-1060
Mail Code 543



Change of Name -
Mobil Oil Corporation to
ExxonMobil Oil Corporation

Dear Ms. Denetsone:

Effective June 1, 2001, Mobil Oil Corporation (MOC) changed its name to ExxonMobil Oil Corporation (EMOC). This was a name change only; EMOC is the same corporation as Mobil Oil Corporation, but with a new name. No facility or other asset was transferred from one corporation to another by virtue of the name change. Specifically, EMOC will remain the owner and operator of its existing exploration and production oil and gas properties and facilities, as well as relevant permits.

There is no change to the name of Exxon Mobil Corporation, the ultimate shareholder of EMOC.

Please note the change of name of MOC to ExxonMobil Oil Corporation in your records pertaining to any MOC permits.

The Federal Identification Number for MOC (13-5401570) will remain the same for EMOC.

Attached is the Name Change Certification, Current listing of Officers and Directors, Filing Fee of \$75/-. Listing of Leases, Financial Statement and a copy of the Rider for Bond number 8027 31 97. The original Bond Rider has been sent to Ms. Barbar Davis at your Washington Office.


If you have any questions, please contact Alex Correa at (713) 431-1012.

Very truly yours,

Charlotte H. Harper

Charlotte H. Harper
Permitting Supervisor

Attachments



ExxonMobil Production Company
a division of Exxon Mobil Corporation,
acting for ExxonMobil Oil Corporation

NOTE: Check forwarded to Ella Isaac

Bureau of Indian Affairs
Navajo Region Office
Attn: RRES - Mineral and Mining Section
P.O. Box 1060
Gallup, New Mexico 87305-1060

Gentlemen:

The current listing of officers and director of ExxonMobil Oil Corporation (Name of Corporation), of New York (State) is as follows:

OFFICERS

President	<u>F.A. Risch</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>
Vice President	<u>K.T. Koonce</u>	Address <u>800 Bell Street Houston, TX 77002</u>
Secretary	<u>F.L. Reid</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>
Treasure	<u>B.A. Maher</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>

DIRECTORS


Name	<u>D.D. Humphreys</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>
Name	<u>P.A. Hanson</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>
Name	<u>T.P. Townsend</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>
Name	<u>B.A. Maher</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>
Name	<u>F.A. Risch</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>


Sincerely,



Alex Correa

This is to certify that the above information pertaining to ExxonMobil Oil Corporation (Corporation) is true and correct as evidenced by the records and accounts covering business for the State of Utah and in the custody of Corporation Service Company (Agent), Phone: 1 (800) 927-9800 whose business address is One Utah Center, 201 South Main Street, Salt Lake City, Utah 84111-2218





Signature
AGENT AND ATTORNEY IN FACT

Title

SAL

CERTIFICATION

I, the undersigned Assistant Secretary of ExxonMobil Oil Corporation. (formerly Mobil Oil Corporation), a corporation organized and existing under the laws of the State of New York, United States of America, DO HEREBY CERTIFY, That, the following is a true and exact copy of the resolutions adopted by the Board of Directors on May 22, 2001:

CHANGE OF COMPANY NAME

WHEREAS, the undersigned Directors of the Corporation deem it to be in the best interest of the Corporation to amend the Certificate of Incorporation of the Corporation to change the name and principal office of the Corporation:

NOW THEREFORE BE IT RESOLVED, That Article 1st relating to the corporate name is hereby amended to read as follows:

"1st The corporate name of said Company shall be,

ExxonMobil Oil Corporation",

FURTHER RESOLVED, That the amendment of the Corporation's Certificate of Incorporation referred to in the preceding resolutions be submitted to the sole shareholder of the Corporation entitled to vote thereon for its approval and, if such shareholder gives its written consent, pursuant to Section 803 of the Business Corporation Law of the State of New York, approving such amendment, the proper officers of the Corporation be, and they hereby are, authorized to execute in the name of the Corporation the Certificate of Amendment of Certificate of Incorporation, in the form attached hereto;


FURTHER RESOLVED, That the proper officers of the Corporation be and they hereby are authorized and directed to deliver, file and record in its behalf, the Certificate of Amendment of Certificate of Incorporation, and to take such action as may be deemed necessary or advisable to confirm and make effective in all respects the change of this Company's name to EXXONMOBIL OIL CORPORATION.


WITNESS, my hand and the seal of the Corporation at Irving, Texas, this 8th day of June, 2001.


Assistant Secretary

COUNTY OF DALLAS)
STATE OF TEXAS)
UNITED STATES OF AMERICA)

Sworn to and subscribed before me at Irving, Texas, U. S. A. on this the 8th day of June, 2001.


Notary Public



LISTING OF LEASES OF MOBIL OIL CORPORATION**Lease Number**

- 1) 14-20-0603-6504
- 2) 14-20-0603-6505
- 3) 14-20-0603-6506
- 4) 14-20-0603-6508
- 5) 14-20-0603-6509
- 6) 14-20-0603-6510
- 7) 14-20-0603-7171
- 8) 14-20-0603-7172A
- 9) 14-20-600-3530
- 10) 14-20-603-359
- 11) 14-20-603-368
- 12) 14-20-603-370
- 13) 14-20-603-370A
- 14) 14-20-603-372
- 15) 14-20-603-372A
- 16) 14-20-603-4495
- 17) 14-20-603-5447
- 18) 14-20-603-5448
- 19) 14-20-603-5449
- 20) 14-20-603-5450
- 21) 14-20-603-5451

6/1/01

CHUBB GROUP OF INSURANCE COMPANIES

One Chubb Plaza, Suite 1900, Houston, Texas 77027-3301
Telephone: (713) 297-4600 • Facsimile: (713) 297-4750

NW Bond

FEDERAL INSURANCE COMPANY RIDER
to be attached to and form a part of

BOND NO 8027 31 97

wherein

Mobil Oil Corporation and Mobil Exploration and Producing U.S., Inc. is
named as Principal and

FEDERAL INSURANCE COMPANY AS SURETY,

in favor of **United States of America, Department of the Interior**
Bureau of Indian Affairs

in the amount of **\$150,000.00**
bond date: 11/01/65

IT IS HEREBY UNDERSTOOD AND AGREED THAT effective June 1, 2001
the name of the Principal is changed

FROM: Mobil Oil Corporation and Mobil Exploration and Producing U.S., Inc.

TO : ExxonMobil Oil Corporation

All other terms and conditions of this Bond are unchanged.

Signed, sealed and dated this 12th of June, 2001.

ExxonMobil Oil Corporation

By: 

FEDERAL INSURANCE COMPANY

By: 

Mary Pierson, Attorney-in-fact

**Chubb
Surety****POWER
OF
ATTORNEY****Federal Insurance Company
Vigilant Insurance Company
Pacific Indemnity Company****Attn.: Surety Department
15 Mountain View Road
Warren, NJ 07059**

Know All by These Presents, That **FEDERAL INSURANCE COMPANY**, an Indiana corporation, **VIGILANT INSURANCE COMPANY**, a New York corporation, and **PACIFIC INDEMNITY COMPANY**, a Wisconsin corporation, do each hereby constitute and appoint

Mary Pierson, Philana Berros, and Jody E. Specht of Houston, Texas----- **R.F. Bobo,**

each as their true and lawful Attorney-in-Fact to execute under such designation in their names and to affix their corporate seals to and deliver for and on their behalf as surety thereon or otherwise, bonds and undertakings and other writings obligatory in the nature thereof (other than bail bonds) given or executed in the course of business, and any instruments amending or altering the same, and consents to the modification or alteration of any instrument referred to in said bonds or obligations.

In Witness Whereof, said **FEDERAL INSURANCE COMPANY**, **VIGILANT INSURANCE COMPANY**, and **PACIFIC INDEMNITY COMPANY** have each executed and attested these presents and affixed their corporate seals on this 10th day of May, 2001.

Kenneth C. Wendel, Assistant Secretary

Frank E. Robertson, Vice President

STATE OF NEW JERSEY } ss.
County of Somerset

On this 10th day of May, 2001

to me known to be Assistant Secretary of **FEDERAL INSURANCE COMPANY**, **VIGILANT INSURANCE COMPANY**, and **PACIFIC INDEMNITY COMPANY**, the companies which executed the foregoing Power of Attorney, and the said Kenneth C. Wendel being by me duly sworn, did depose and say that he is Assistant Secretary of **FEDERAL INSURANCE COMPANY**, **VIGILANT INSURANCE COMPANY**, and **PACIFIC INDEMNITY COMPANY**, and knows the corporate seals thereof, that the seals affixed to the foregoing Power of Attorney are such corporate seals and were thereto affixed by authority of the By-Laws of said Companies; and that he is acquainted with Frank E. Robertson, and knows him to be Vice President of said Companies; and that the signature of Frank E. Robertson, subscribed to said Power of Attorney is in the genuine handwriting of Frank E. Robertson, and was thereto subscribed by authority of said Companies in the presence of



Notary Public State of New Jersey
No. 2231647

Commission Expires Oct. 28, 2004

Karen A. Price
Notary Public

Extract from the By-Laws of **FEDERAL INSURANCE COMPANY**, **VIGILANT INSURANCE COMPANY**, and **PACIFIC INDEMNITY COMPANY**:

"All powers of attorney for and on behalf of the Company may and shall be executed in the name and on behalf of the Company, either by the Chairman or the President or a Vice President or an Assistant Vice President, jointly with the Secretary or an Assistant Secretary, under their respective designations. The signature of such officers may be engraved, printed or lithographed. The signature of each of the following officers: Chairman, President, any Vice President, any Assistant Vice President, any Secretary, any Assistant Secretary and the seal of the Company may be affixed by facsimile to any power of attorney or to any certificate relating thereto appointing Assistant Secretaries or Attorneys-In-Fact for purposes only of executing and attesting bonds and undertakings and other writings obligatory in the nature thereof, and any such power of attorney or certificate bearing such facsimile signature or facsimile seal shall be valid and binding upon the Company and any such power so executed and certified by such facsimile signature and facsimile seal shall be valid and binding upon the Company with respect to any bond or undertaking to which it is attached."

I, Kenneth C. Wendel, Assistant Secretary of **FEDERAL INSURANCE COMPANY**, **VIGILANT INSURANCE COMPANY**, and **PACIFIC INDEMNITY COMPANY** (the "Companies") do hereby certify that

- (i) the foregoing extract of the By-Laws of the Companies is true and correct,
- (ii) the Companies are duly licensed and authorized to transact surety business in all 50 of the United States of America and the District of Columbia and are authorized by the U. S. Treasury Department; further, Federal and Vigilant are licensed in Puerto Rico and the U. S. Virgin Islands, and Federal is licensed in American Samoa, Guam, and each of the Provinces of Canada except Prince Edward Island; and
- (iii) the foregoing Power of Attorney is true, correct and in full force and effect.

Given under my hand and seals of said Companies at Warren, NJ this 12th day of June, 2001



Kenneth C. Wendel, Assistant Secretary

IN THE EVENT YOU WISH TO NOTIFY US OF A CLAIM, VERIFY THE AUTHENTICITY OF THIS BOND OR NOTIFY US OF ANY OTHER MATTER, PLEASE CONTACT US AT ADDRESS LISTED ABOVE, OR BY
Telephone (908) 903-3485 Fax (908) 903-3656 e-mail: surety@chubb.com

CSC

5184334741

06/01 '01 08:46 NO.410 03/05

CSC

06/01 '01 09:06 NO.135 02/04

F010601000187

CERTIFICATE OF AMENDMENT
OF
CERTIFICATE OF INCORPORATION
OF
MOBIL OIL CORPORATION

CSC 45

(Under Section 805 of the Business Corporation Law)

Pursuant to the provisions of Section 805 of the Business Corporation Law, the undersigned President and Secretary, respectively, of Mobil Oil Corporation hereby certify:

FIRST: That the name of the corporation is MOBIL OIL CORPORATION and that said corporation was incorporated under the name of Standard Oil Company of New York.

SECOND: That the Certificate of Incorporation of the corporation was filed by the Department of State, Albany, New York, on the 10th day of August, 1882.

THIRD: That the amendments to the Certificate of Incorporation effected by this Certificate are as follows:

(a) Article 1st of the Certificate of Incorporation, relating to the corporate name, is hereby amended to read as follows:

"1st The corporate name of said Company shall be,
ExxonMobil Oil Corporation",

(b) Article 7th of the Certificate of Incorporation, relating to the office of the corporation is hereby amended to read as follows:

The office of the corporation within the State of New York is to be located in the County of Albany. The Company shall have offices at such other places as the Board of Directors may from time to time determine.

CSC
CSC

5184334741

06/01 '01 08:47 NO.410 04/05
06/01 '01 09:06 NO.133 03/04

FOURTH: That the amendments to the Certificate of Incorporation were authorized by the Board of Directors followed by the holder of all outstanding shares entitled to vote on amendments to the Certificate of Incorporation by written consent of the sole shareholder dated May 22, 2001.

IN WITNESS WHEREOF, this Certificate has been signed this 22nd Day of May, 2001.


F. A. Ritch, President

STATE OF TEXAS)
COUNTY OF DALLAS)


F. L. REID, being duly sworn, deposes and says that he is the Secretary of MOBIL OIL CORPORATION, the corporation mentioned and described in the foregoing instrument; that he has read and signed the same and that the statements contained therein are true.


F. L. REID, Secretary

SUBSCRIBED AND SWORN TO before me, the undersigned authority, on this the 22nd day of May, 2001.

[SEAL]


NOTARY PUBLIC, STATE OF TEXAS



=> CSC

.TEL=5184334741

06/01'01 08:19

CSC
CSC

5184334741

06/01 '01 09:01 NO.411 02/02
06/01 '01 09:06 NO.133 04/04
F010601000187**CSC 45****CERTIFICATE OF AMENDMENT****OF****MOBIL OIL CORPORATION**


Under Section 805 of the Business Corporation Law

*SAC***STATE OF NEW YORK
DEPARTMENT OF STATE**Filed by: EXXONMOBIL CORPORATION
(Name)

FILED JUN 01 2001

6949 Las Colinas Blvd.
(Mailing address)

TAX \$

BY: *SAC*Irving, TX 75039-2298
(City, State and Zip code)*ny Albany**Cust Ref # 1655781MPJ***010601000195**

=> CSC

TEL=5184334741

06/01 '01 08:19

State of New York }
Department of State } ss:

I hereby certify that the annexed copy has been compared with the original document in the custody of the Secretary of State and that the same is a true copy of said original.

Witness my hand and seal of the Department of State on **JUN 01 2001**



A handwritten signature in black ink, appearing to read "J. Leuch", followed by a long horizontal line extending to the right.

Special Deputy Secretary of State

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH

2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent

X Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective: **06-01-2001**

FROM: (Old Operator):	TO: (New Operator):
MOBIL EXPLORATION & PRODUCTION	EXXONMOBIL OIL CORPORATION
Address: P O BOX DRAWER "G"	Address: U S WEST P O BOX 4358
CORTEZ, CO 81321	HOUSTON, TX 77210-4358
Phone: 1-(970)-564-5212	Phone: 1-(713)-431-1010
Account No. N7370	Account No. N1855

CA No.

Unit:

RATHERFORD

WELL(S)

NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
RATHERFORD UNIT 17-33	17-41S-24E	43-037-31134	6280	INDIAN	OW	P
RATHERFORD UNIT 17-11	17-41S-24E	43-037-31169	6280	INDIAN	OW	S
RATHERFORD UNIT 17-22	17-41S-24E	43-037-31170	6280	INDIAN	OW	P
RATHERFORD UNIT 17-42	17-41S-24E	43-037-31177	6280	INDIAN	OW	P
RATHERFORD UNIT 17-31	17-41S-24E	43-037-31178	6280	INDIAN	OW	P
18-11	18-41S-24E	43-037-15733	6280	INDIAN	OW	P
RATHERFORD 18-13	18-41S-24E	43-037-15734	6280	INDIAN	OW	P
RATHERFORD UNIT 18-44	18-41S-24E	43-037-31045	6280	INDIAN	OW	P
RATHERFORD UNIT 18-24	18-41S-24E	43-037-31079	6280	INDIAN	OW	P
RATHERFORD UNIT 18-33	18-41S-24E	43-037-31135	6280	INDIAN	OW	P
RATHERFORD UNIT 18-31	18-41S-24E	43-037-31181	6280	INDIAN	OW	P
RATHERFORD UNIT 18-42	18-41S-24E	43-037-31182	6280	INDIAN	OW	P
RATHERFORD UNIT 18-22	18-41S-24E	43-037-31236	6280	INDIAN	OW	P
19-42	19-41S-24E	43-037-30916	6280	INDIAN	OW	P
RATHERFORD UNIT 19-22	19-41S-24E	43-037-31046	6280	INDIAN	OW	P
RATHERFORD UNIT 19-31	19-41S-24E	43-037-31047	6280	INDIAN	OW	P
RATHERFORD UNIT 19-33	19-41S-24E	43-037-31048	6280	INDIAN	OW	P
RATHERFORD UNIT 19-11	19-41S-24E	43-037-31080	6280	INDIAN	OW	P
RATHERFORD UNIT 19-44	19-41S-24E	43-037-31081	6280	INDIAN	OW	P
RATHERFORD 19-97	19-41S-24E	43-037-31596	6280	INDIAN	OW	P

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 06/29/2001
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 06/29/2001
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 04/09/2002
4. Is the new operator registered in the State of Utah: YES Business Number: 579865-0143
5. If **NO**, the operator was contacted on: N/A

6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BIA-06/01/01

7. **Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: 06/01/2001

8. **Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: N/A

9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 04/15/2002
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 04/15/2002
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: N/A

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: N/A

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: 80273197

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number N/A
2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ
2. CDW

X Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective: **6/1/2006**

FROM: (Old Operator): N1855-ExxonMobil Oil Corporation PO Box 4358 Houston, TX 77210-4358 Phone: 1 (281) 654-1936	TO: (New Operator): N2700-Resolute Natural Resources Company 1675 Broadway, Suite 1950 Denver, CO 80202 Phone: 1 (303) 534-4600
CA No.	Unit: RATHERFORD

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 4/21/2006
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 4/24/2006
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 6/7/2006
- Is the new operator registered in the State of Utah: YES Business Number: 5733505-0143
- If **NO**, the operator was contacted on: _____
- 6a. (R649-9-2) Waste Management Plan has been received on: requested
- 6b. Inspections of LA PA state/fee well sites complete on: n/a
- 6c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM n/a BIA not yet
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: not yet
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 6/12/2006

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 6/22/2006
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 6/22/2006
- Bond information entered in RBDMS on: n/a
- Fee/State wells attached to bond in RBDMS on: n/a
- Injection Projects to new operator in RBDMS on: 6/22/2006
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: n/a
- Indian well(s) covered by Bond Number: PA002769
- (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number n/a
- The **FORMER** operator has requested a release of liability from their bond on: n/a
The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

See attached list

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

Navajo Tribe

7. UNIT or CA AGREEMENT NAME:

Ratherford Unit

8. WELL NAME and NUMBER:

See attached list

9. API NUMBER:

Attached

10. FIELD AND POOL, OR WILDCAT:

Greater Aneth

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☐

OTHER Unit Agreement

2. NAME OF OPERATOR:

Resolute Natural Resources Company

N2700

3. ADDRESS OF OPERATOR:

1675 Broadway, Suite 1950

CITY

Denver

STATE

CO

ZIP

80202

PHONE NUMBER:

(303) 534-4600

4. LOCATION OF WELL

FOOTAGES AT SURFACE: See attached list

COUNTY: San Juan

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ NOTICE OF INTENT
(Submit in Duplicate)

Approximate date work will start:

☒ SUBSEQUENT REPORT
(Submit Original Form Only)

Date of work completion:

TYPE OF ACTION

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☒ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☐ OTHER: _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective June 1, 2006 Exxon Mobil Oil Corporation resigns as operator of the Ratherford Unit. Also effective June 1, 2006 Resolute Natural Resources Company is designated as successor operator of the Ratherford Unit.

A list of affected producing and water source wells is attached. A separate of affected injection wells is being submitted with UIC Form 5, Transfer of Authority to Inject.

As of the effective date, bond coverage for the affected wells will transfer to BIA Bond # PA002769.

NAME (PLEASE PRINT)

Dwight E Mallory

TITLE

Regulatory Coordinator

SIGNATURE

DATE

4/20/2006

(This space for State use only)

APPROVED 6127106

Earlene Russell

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED

APR 24 2006

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: Ship Rock
2. NAME OF OPERATOR: ExxonMobil Oil Corporation <i>N1855</i>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ship Rock
3. ADDRESS OF OPERATOR: P.O. Box 4358 CITY Houston STATE TX ZIP 77210-4358		7. UNIT or CA AGREEMENT NAME: UTU68931A
4. LOCATION OF WELL FOOTAGES AT SURFACE: _____ QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: _____		8. WELL NAME and NUMBER: Ratherford
PHONE NUMBER: (281) 654-1936		9. API NUMBER: attached
COUNTY: San Juan		10. FIELD AND POOL, OR WILDCAT: Aneth
STATE: UTAH		

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>6/1/2006</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

ExxonMobil Oil Corporation is transferring operatorship of Greater Aneth field, Ratherford lease to Resolute Natural Resources Company. All change of operator notices should be made effective as of 7:00 AM MST on June 1, 2006.

Attached please find a listing of producers and water source wells included in the transfer.

NAME (PLEASE PRINT) <u>Laurie Kilbride</u>	TITLE <u>Permitting Supervisor</u>
SIGNATURE <i>Laurie B. Kilbride</i>	DATE <u>4/19/2006</u>

(This space for State use only)

APPROVED 6/27/06
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

RECEIVED
APR 21 2006

DIV. OF OIL, GAS & MINING

Ratherford Unit - Producer Well List

minus P&A's

Lease	Number	API #	Status	Lease #	Location					
					Sec	T	R	QTR/QTR	NSFoot	EWFoot
Ratherford	01-14	430373116200S1	Producing	1420603246A	1	41S	23E	SWSW	0660FSL	0660FWL
Ratherford	01-34	430371638501S1	SI	1420603246A	1	41S	23E	SWSE	1133FSL	1980FEL
Ratherford	11-41	430373154400S1	Producing	1420603246A	11	41S	23E	NENE	0860FNL	0350FEL
Ratherford	11-43	430373162201S1	Producing	1420603246A	11	41S	23E	NESE	1980FSL	0660FEL
Ratherford	12-12	430373119000S1	Producing	1420603246A	12	41S	23E	SWNW	1850FNL	0660FWL
Ratherford	12-14	430371584400S1	SI	1420603246A	12	41S	23E	SWSW	0660FSL	4622FEL
Ratherford	12-21	430373120100S1	Producing	1420603246A	12	41S	23E	NENW	0660FNL	1980FWL
Ratherford	12-23	430371584601S1	Producing	1420603246A	12	41S	23E	NESW	1958FSL	3300FEL
Ratherford	12-32	430373120300S1	Producing	1420603246A	12	41S	23E	SWNE	1820FNL	1820FEL
Ratherford	12-34	430373112600S1	Producing	1420603246A	12	41S	23E	SWSE	0675FSL	1905FEL
Ratherford	12-43	430373120200S1	SI	1420603246A	12	41S	23E	NESE	2100FSL	0660FEL
Ratherford	13-12	430373112701S1	Producing	1420603247A	13	41S	23E	SWNW	1705FNL	0640FWL
Ratherford	13-14	430373158900S1	Producing	1420603247A	13	41S	23E	SWSW	0660FSL	0660FWL
Ratherford	13-21	430373112801S1	SI	1420603247A	13	41S	23E	NENW	0660FNL	1920FWL
Ratherford	13-23	430373112900S1	Producing	1420603247A	13	41S	23E	NESW	1980FSL	1930FWL
Ratherford	13-34	430373113001S1	Producing	1420603247A	13	41S	23E	SWSE	0660FSL	1980FEL
Ratherford	13-41	430371585601S1	Producing	1420603247A	13	41S	23E	NENE	660FNL	660FEL
Ratherford	13-43	430373113100S1	Producing	1420603247A	13	41S	23E	NESE	1700FSL	0960FEL
Ratherford	14-32	430371585801S1	Producing	1420603247A	14	41S	23E	SWNE	2130FNL	1830FEL
Ratherford	14-41	430373162300S1	Producing	1420603247A	14	41S	23E	NENE	0521FNL	0810FEL
Ratherford	24-32	430373159300S1	Producing	1420603247A	24	41S	23E	SWNE	2121FNL	1846FEL
Ratherford	24-41	430373113200S1	Producing	1420603247A	24	41S	23E	NENE	0660FNL	0710FEL
Ratherford	17-11	430373116900S1	Producing	1420603353	17	41S	24E	NWNW	1075FNL	0800FWL
Ratherford	17-13	430373113301S1	Producing	1420603353	17	41S	24E	NWSW	2100FSL	0660FWL
Ratherford	17-22	430373117001S1	Producing	1420603353	17	41S	24E	SENE	1882FNL	1910FWL
Ratherford	17-24	430373104400S1	Producing	1420603353	17	41S	24E	SESW	0720FSL	1980FWL
Ratherford	17-31	430373117800S1	Producing	1420603353	17	41S	24E	NWNE	0500FNL	1980FEL
Ratherford	17-33	430373113400S1	Producing	1420603353	17	41S	24E	NWSE	1980FSL	1845FEL
Ratherford	17-42	430373117700S1	Producing	1420603353	17	41S	24E	SENE	1980FNL	0660FEL
Ratherford	17-44	430371573201S1	Producing	1420603353	17	41S	24E	SESE	0660FSL	0660FEL
Ratherford	18-11	430371573300S1	SI	1420603353	18	41S	24E	NWNW	0720FNL	0730FWL
Ratherford	18-13	430371573401S1	Producing	1420603353	18	41S	24E	NWSW	1980FSL	0500FWL
Ratherford	18-22	430373123600S1	Producing	1420603353	18	41S	24E	SENE	2200FNL	2210FWL
Ratherford	18-24	430373107900S1	Producing	1420603353	18	41S	24E	SESW	0760FSL	1980FWL
Ratherford	18-31	430373118101S1	Producing	1420603353	18	41S	24E	NWNE	0795FNL	2090FEL
Ratherford	18-33	430373113501S1	Producing	1420603353	18	41S	24E	NWSE	1870FSL	1980FEL
Ratherford	18-42	430373118200S1	Producing	1420603353	18	41S	24E	SENE	2120FNL	0745FEL
Ratherford	18-44	430373104500S1	SI	1420603353	18	41S	24E	SESE	0660FSL	0660FEL
Ratherford	19-11	430373108000S1	Producing	1420603353	19	41S	24E	NWNW	0660FNL	0660FWL
Ratherford	19-13	430373171900S1	Producing	1420603353	19	41S	24E	NWSW	1980FSL	0660FWL
Ratherford	19-22	430373104601S1	Producing	1420603353	19	41S	24E	SENE	1840FNL	1980FWL
Ratherford	19-24	430373175401S1	Producing	1420603353	19	41S	24E	SESW	0600FSL	1980FWL
Ratherford	19-31	430373104701S1	Producing	1420603353	19	41S	24E	NWNE	510FNL	1980FEL
Ratherford	19-33	430373104800S1	Producing	1420603353	19	41S	24E	NWSE	1980FSL	1980FEL
Ratherford	19-42	430373091600S1	Producing	1420603353	19	41S	24E	SENE	1880FNL	0660FEL
Ratherford	19-44	430373108100S1	Producing	1420603353	19	41S	24E	SESE	0660FSL	0660FEL
Ratherford	19-97	430373159600S1	Producing	1420603353	19	41S	24E	SENE	2562FNL	0030FEL
Ratherford	20-11	430373104900S1	Producing	1420603353	20	41S	24E	NWNW	0500FNL	0660FWL
Ratherford	20-13	430373091700S1	Producing	1420603353	20	41S	24E	NWSW	2140FSL	0500FWL
Ratherford	20-22	430373093000S1	Producing	1420603353	20	41S	24E	SENE	2020FNL	2090FWL
Ratherford	20-24	430373091800S1	Producing	1420603353	20	41S	24E	SESW	0820FSL	1820FWL

Ratherford Unit - Producer Well List

minus P&A's

Lease	Number	API #	Status	Lease #	Location					
					Sec	T	R	QTR/QTR	NSFoot	EWFoot
Ratherford	20-31	430373105001S1	Producing	1420603353	20	41S	24E	NWNE	0660FNL	1880FEL
Ratherford	20-33	430373093100S1	Producing	1420603353	20	41S	24E	NWSE	1910FSL	2140FEL
Ratherford	20-42	430373105100S1	Producing	1420603353	20	41S	24E	SENE	1980FNL	0660FEL
Ratherford	20-44	430373091501S1	Producing	1420603353	20	41S	24E	SESE	0620FSL	0760FEL
Ratherford	20-66	430373159201S1	Producing	1420603353	20	41S	24E	SWNW	1369FNL	1221FWL
Ratherford	20-68	430373159100S1	Producing	1420603353	20	41S	24E	NWSW	1615FSL	1276FWL
Ratherford	15-12	430371571501S1	Producing	1420603355	15	41S	24E	SWNW	1820FNL	0500FWL
Ratherford	15-22	430373044900S1	SI	1420603355	15	41S	24E	SENE	1980FNL	2050FWL
Ratherford	15-32	430371571700S1	Producing	1420603355	15	41S	24E	SWNE	1980FNL	1980FEL
Ratherford	15-33	430371571800S1	Producing	1420603355	15	41S	24E	NWSE	1650FSL	1980FEL
Ratherford	15-41	430371571900S1	TA	1420603355	15	41S	24E	NENE	0660FNL	0660FEL
Ratherford	15-42	430373044800S1	Producing	1420603355	15	41S	24E	SENE	2020FNL	0820FEL
Ratherford	16-13	430373116801S1	Producing	1420603355	16	41S	24E	NWSW	1980FSL	660FWL
Ratherford	16-32	430371572300S1	Producing	1420603355	16	41S	24E	SWNE	1980FNL	1980FEL
Ratherford	16-41	430371572500S1	Producing	1420603355	16	41S	24E	NENE	0660FNL	0660FEL
Ratherford	16-77	430373176800S1	Producing	1420603355	16	41S	24E	NESW	2587FSL	2410FWL
Ratherford	21-23	430371375400S1	Producing	1420603355	21	41S	24E	NESW	1740FSL	1740FWL
Ratherford	21-24	430373172001S1	SI	1420603355	21	41S	24E	SESW	487FSL	2064FWL
Ratherford	21-32	430371575500S1	SI	1420603355	21	41S	24E	SWNE	1880FNL	1980FEL
Ratherford	21-77	430373175801S1	SI	1420603355	21	41S	24E	NWSE	2511FSL	2446FEL
Ratherford	07-11	430373116300S1	Producing	1420603368	7	41S	24E	NWNW	0660FNL	0710FWL
Ratherford	07-13	430373116400S1	Producing	1420603368	7	41S	24E	NWSW	2110FSL	0740FWL
Ratherford	07-22	430373116500S1	Producing	1420603368	7	41S	24E	SENE	1980FNL	1980FWL
Ratherford	07-24	430373116600S1	Producing	1420603368	7	41S	24E	SESW	0880FSL	2414FWL
Ratherford	07-44	430373118900S1	SI	1420603368	7	41S	24E	SESE	0737FSL	0555FEL
Ratherford	08-12	430371599100S1	Producing	1420603368	8	41S	24E	SWNW	1909FNL	0520FWL
Ratherford	08-21	430371599300S1	Producing	1420603368	8	41S	24E	NENW	0616FNL	1911FWL
Ratherford	08-23	430371599400S1	Producing	1420603368	8	41S	24E	NESW	1920FSL	2055FWL
Ratherford	08-32	430371599500S1	Producing	1420603368	8	41S	24E	SWNE	1980FNL	1980FEL
Ratherford	08-34	430371599600S1	Producing	1420603368	8	41S	24E	SWSE	0660FSL	1980FEL
Ratherford	04-34	430371616400S1	Producing	14206034035	4	41S	24E	SWSE	0660FSL	1980FEL
Ratherford	11-14	430371616700S1	Producing	14206034037	11	41S	24E	SWSW	0660FSL	0660FWL
Ratherford	09-34	430371571100S1	SI	14206034043	9	41S	24E	SWSE	0660FSL	1980FEL
Ratherford	10-12	430371571200S1	Producing	14206034043	10	41S	24E	SWNW	1980FNL	0660FWL
Ratherford	10-14	430371571300S1	Producing	14206034043	10	41S	24E	SWSW	0510FSL	0710FWL
Ratherford	10-32	430371571400S1	TA	14206034043	10	41S	24E	SWNE	2080FNL	1910FEL
Ratherford	10-44	430373045100S1	TA	14206034043	10	41S	24E	SESE	0820FSL	0510FEL
Ratherford	29-11	430373105300S1	Producing	1420603407	29	41S	24E	NWNW	0770FNL	0585FWL
Ratherford	29-22	430373108200S1	Producing	1420603407	29	41S	24E	SENE	2130FNL	1370FWL
Ratherford	29-31	430373091401S1	Producing	1420603407	29	41S	24E	NWNE	0700FNL	2140FEL
Ratherford	29-33	430373093200S1	SI	1420603407	29	41S	24E	NWSE	1860FSL	1820FEL
Ratherford	29-34	430371534000S1	SI	1420603407	29	41S	24E	SWSE	0817FSL	2096FEL
Ratherford	29-42	430373093700S1	SI	1420603407	29	41S	24E	SENE	1850FNL	0660FEL
Ratherford	30-32	430371534200S1	Producing	1420603407	30	41S	24E	SWNE	1975FNL	2010FEL
Ratherford	28-11	430373044600S1	Producing	1420603409	28	41S	24E	NWNW	0520FNL	0620FWL

Ratherford Unit - Producer Well List

minus P&A's

Lease	Number	API #	Status	Lease #	Location					
					Sec	T	R	QTR/QTR	NSFoot	EWFoot
Ratherford	09-12	430371512600S1	Producing	14206035045	9	41S	24E	SWNW	1865FNL	0780FWL
Ratherford	09-14	430371512700S1	Producing	14206035046	9	41S	24E	SWSW	0695FSL	0695FWL
Ratherford	04-14	430371616300S1	Producing	14206035446	4	41S	24E	SWSW	0500FSL	0660FWL
Ratherford	03-12	430371562000S1	Producing	14206036506	3	41S	24E	SWNW	2140FNL	0660FWL

Water Source Wells (Feb 2006)

RU	S1	4303700001	Active
RU	S2	4303700002	Active
RU	S3	4303700003	Active
RU	S4	4303700004	Active
RU	S5	4303700005	Active
RU	S6	4303700006	Active
RU	S7	4303700007	Active
RU	S8	4303700008	Active
RU	S9	4303700009	Active
RU	S10	4303700010	Active
RU	S11	4303700011	Active
RU	S12	4303700012	Active
RU	S13	4303700013	Active
RU	S14	4303700014	Active
RU	S16	4303700016	Active
RU	S17	4303700017	Active